



SYMBOL KEY	
	TWIN POWER SOCKET OUTLET AT SKIRTING LEVEL
	TWIN POWER SOCKET OUTLET WITHIN FURNITURE/JONERY
	TELEPHONE POINT AT SKIRTING LEVEL
	DATA POINT AT SKIRTING LEVEL
	RADIATOR

NOTES:

ALL FIXINGS:

Listed Building: Great care must be taken while checking existing fixing points and establishing new ones during strip-out.

Contractor to visit site to establish and mark out fixing positions prior to fit out.

Once stripped out, contractor to liaise with design consultant, planning consultant and client for a visit with Listed Buildings, who will inspect and agree on fixings prior to any installation.

All fixings in accordance with detail drawings and 27302.0 Method Statement

Area will have new finishes in situ such as floor, decorations, lighting and power. All to be protected during fit out period.

Make good any decorations marked during fit out.

GENERAL POWER NOTES:

Existing power fittings and locations not shown.

Contractor to survey existing power and pick up and reuse where possible.

Contractor to liaise with client to establish and position: security alarms, smoke alarms, CCTV and speaker system for specification, details and requirements, along with all other items not listed below.

No chasing in walls and ceilings, conduits to be concealed in or behind cabinetry where possible.

Grey lines indicate outline of fit out furniture layout. Refer to 27302.0 GA and setting out

Lighting to be supplied and installed in accordance with the specification provided by Iuzzini. Contractor to liaise with supplier on power requirements and fixings. See 004.0 for RCP and lighting specification. www.iuzzini.com

Socket positions shown where new walls are positioned, to be brought to new wall front and socket plate and height to match those elsewhere. See 27319.1.0, 273102.0, 27319.0 and 273302.0 for setting out. To be agreed and finalised on site.

FLOORING:

Rooms 66a, 67 and 68: Contractor to allow for removal of existing floor and making good/preparation for new grey marmoleum or similar to match existing throughout. To be agreed with client and design consultant.

- ITEMS:**
- 1/ Cash Desk. All equipment free issue by client. Client to provide equipment list and relevant specification. Contractor to ensure sufficient power and data is provided for flexibility and ease of use. Flex cable management, and all cables to be concealed within new features. See 273301.0 and 273302.0 for cash desk and back wall details.
- 2/ Panic alarm to be fitted within cash desk unit. Final position to be agreed on site.
- 3/ Wall sockets to be face mounted onto new features. Contractor to ensure power, data and telephone sockets positioned to match heights elsewhere. To be agreed and finalised on site. Radiator position to be agreed on site.
- 4/ Freestanding display cabinet with power for concealed LED strip lighting recessed into side faces. Iuzzini to specify LED fittings. Socket and switch at low level. Contractor to liaise with supplier on installation and power requirements. www.iuzzini.com See 273407.0 for cabinet detail and 273004.0 for RCP and lighting specification.
- 5/ Indicates customer on line touch screen. This may be an iPad in this location etc. Screen and hardware to be supplied free issue by client. Client to provide information on equipment specification. Contractor to fit within shop fit elements. Currently proposed is an iPad in bouncemap mount etc. Refer to 273091.0 for position.
- 6/ Indicates customer print on demand (POD) facility. This is by way of a touch screen interactive. Client to supply equipment free issue along with relevant information. Currently proposed is an iPad in bouncemap mount etc. Contractor to fit equipment within shop fit element. Refer to drawing 273215.0
- 7/ DVD reglery unit. Equipment and spec. all by client to be advised. Contractor to fit within shop fit unit. Proposed 1x screen 1x dvd player 1x phone sound adaptor all to be confirmed. Refer to drawing 273210.0
- 8/ New hung illuminated FE sign, with power in galvanised conduit cables. Iuzzini to specify new sign. Contractor to investigate behind FE sign and liaise with supplier for installation requirements and detail. www.iuzzini.com Refer to 273004.0 for RCP layout and specification.
- 9/ LCD screen to be hard wired to pegboard wall. Screen supplied free issue. Contractor to ensure power supply is extended, and to fit screen
- 10/ Freestanding display window unit with power for concealed LED lighting recessed into side faces and top. Iuzzini to specify LED fittings. Socket and switch at low level. Contractor to liaise with supplier on installation and power requirements. www.iuzzini.com See 273217.0 for cabinet detail and 273004.0 for RCP and lighting specification.

RADIATORS:

Electric radiators, with thermostat timer on fused spur. Painted out to match underlay.

Radiator positions shown indicatively concealed where possible within new features. Radiator proposal sufficient for heating all rooms to be developed by main contractor. See 273218.1 Curved wall base unit, 273219.0 and 273102.0 Internal Elevations, and 273301.0 and 273302.0 Cash Desk drawings for radiator position details and locations on new features.

- R1 Radiator fixed to existing wall. Contractor to advise on size suitable for heating Room 66a
- R2 Radiator fixed to cash desk graphic back wall. Contractor to advise on width suitable for heating Room 67, and to ensure radiator is not visible from shop floor
- R3 Small radiator fixed inside low storage unit on wall bay. Grilles to front of storage unit, radiator accessible via unit pull doors. See 273218.1 for elevation. Contractor to ensure spec size and install suitable for existing base unit detail
- R4 Radiator fixed to cash desk graphic back wall. Contractor to advise on width suitable for heating Room 67, and to ensure radiator is not visible from shop floor

DRINKALLDEAN

Ground Floor 32 St Oswalds Place London SE11 5JE
PHONE: +44 (0) 207 735 2731
info@drinkalldean.co.uk www.drinkalldean.co.uk

GENERAL NOTES		DRAWING STATUS: FOR TENDER	CLIENT: CHURCHILL WAR ROOMS	DRAWING TITLE: Small power and flooring
NOT SCALE FROM THIS DRAWING. NOTES TO WRITTEN DIMENSIONS ONLY. ALL DIMENSIONS AND LEVELS TO BE CHECKED ON SITE BY THE CONTRACTOR. FROM TO COMMENCEMENT OF WORKS. ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER IMMEDIATELY AND PRIOR TO COMMENCEMENT OF WORKS. ALL DIMENSIONS TO BE READ FROM PLANVIEW WITH WRITTEN DIMENSIONS. DIMENSIONS SUPPLIED BY THE DESIGNER.				
ALL DIMENSIONS TO BE READ IN CONJUNCTION WITH CONSULTANTS' DIMENSIONS AND DRAWINGS. ANY DISCREPANCIES BETWEEN CONSULTANTS' DIMENSIONS TO BE REPORTED TO THE DESIGNER PRIOR TO COMMENCEMENT OF WORKS.		REVISIONS:	PROJECT ADDRESS: CWR Shop	PAPER SIZE: A2
THIS DRAWING SHOWS THE DESIGN INTENT (NOT) THE CONTRACTOR SHALL ADVISE ON ALL DETAILS AND INSURE STRENGTH AND STABILITY IN ALL CONSTRUCTION.				
THE CONTRACTOR TO PROVIDE SETTING OUT AND RED DRAWINGS FOR APPROVAL, PRIOR TO CONSTRUCTION.		DATE: 27/03/20	DRAWN BY: CJ	DATE: Sept 2015
ALL SERVICES TO COMPLY WITH LOCAL AUTHORITY BUILDING CONTROL AND ENVIRONMENTAL HEALTH REQUIREMENTS AND TO BE VERIFIED BY THE DESIGNER.				
ALL STRUCTURE TO LOCAL AUTHORITY AND BUILDING CONTROL, REQUIREMENTS AND TO STRUCTURAL ENGINEERS' DETAILS AND CALCULATIONS.		DATE: 27/03/20	DRAWN BY: CJ	DATE: Sept 2015
DO NOT SCALE THIS DRAWING. CHECK ALL DIMENSIONS ON SITE.				
THE CONTRACTOR SHALL COMPLY WITH CONSTRUCTION SAFETY REGULATIONS, CODE OF PRACTICE FOR THE PREVENTION OF FALLS ON CONSTRUCTION SITES AND ALL APPLICABLE REGULATIONS AND STANDARDS.		DATE: 27/03/20	DRAWN BY: CJ	DATE: Sept 2015
ALL CONSTRUCTION AND MATERIALS TO CONFORM TO CURRENT BUILDING AND FIRE REGULATIONS.				
SITE WASTE MANAGEMENT: THE CONTRACTOR SHALL MANAGE ALL WASTE MATERIALS AND RE-USE / RECYCLE AS MUCH AS POSSIBLE TO MINIMIZE WASTE.		DATE: 27/03/20	DRAWN BY: CJ	DATE: Sept 2015
RISK ASSESSMENT: THE CONTRACTOR MUST ENSURE THAT THE SITE IS A HAZARDOUS TO THE WORKERS. ALL WASTE MATERIALS MUST BE MANAGED IN A SAFE MANNER. THE CONTRACTOR SHALL MANAGE ALL WASTE MATERIALS AND RE-USE / RECYCLE AS MUCH AS POSSIBLE TO MINIMIZE WASTE.				
DATE: 27/03/20		DATE: 27/03/20	DRAWN BY: CJ	DATE: Sept 2015
DATE: 27/03/20				