

- P1. Clay pavers in running bond see 2 product options in notes
- P2. Clay pavers (P1) shallow dished channel
- P3. Concrete pavers to new footway and reinstate around furniture (to match surrounding existing)
- W1. Granite upstand surround with channel inlets into raingarden and street overflows, supplied by CED Stone or simlar approved - see notes for contact. Refer to RF-110-403
- W2. Granite upstand surround, with top seat G2, supplied by CED Stone or simlar approved - see notes for contact. Refer to RF-110-403
- W3. New retaining wall, with partial top seat G3, finished with Staffordshire Light Multi Clay Quarry Tiles by Ketley, vertical running bond. Structure and tanking to engineers specification + drawing RF-110-400
- W4. New retaining wall, to connect with existing, finished with Staffordshire Light Multi Clay Quarry Tiles by Ketley, vertical running bond. Structure and tanking to engineers detail
- W5. Existing retaining wall, refurbished where needed and finished with Staffordshire Light Multi Clay Quarry Tiles by Ketley, vertical running bond. Structure and tanking to engineers detail
- W6. Existing retaining wall, lowered to accommodate rails, refurbished where needed and finished with Staffordshire Light Multi Clay Quarry Tiles by Ketley, vertical running bond. Structure and tanking to engineers detail
- G1. Curved Double sided R&R bench by Streetlife or similar approved - see notes for contacts and refer to drawing: RF-110-402
- G2. Top Seat by Streetlife or similar approved. Partial back rest (approx. 5.4 lin. m) - see notes for contacts and refer to drawing: RF-110-402
- G3. Top Seat by Streetlife or similar approved. No back rest see notes for contacts and refer to drawing: RF-110-402
- G4. Steel / cast iron bollards, product TBC
- G5. Powder coated steel handrail, design tbc
- G6. Powder coated steel knee-rail to match G5, design TBC
- G7. Pop up power supply supply, design TBC
- G8. Allowance for refurbishment of step units
- G9. Allowance for treatment to base of security mast (pending GI)
- K1. Granite upstand kerb, 150mm width, supplied by CED Stone or similar approved - see notes
- K2. Granite flush kerb, 150mm width, supplied by CED Stone or similar approved - see notes
- K3. Granite upstand kerb, 150mm width, supplied by CED Stone or similar approved - see notes TBC (refer to engineers specification for concrete option for comparable costing)
- K4. Granite drop kerb, 150mm width, supplied by CED Stone or similar approved - see notes TBC (refer to engineers specification for concrete option for comparable costing)

- 1. P1 Option 1: Slim format *Tenger Clay Pavers* in Staffordshire Brown Brindle from Ketley; ketley-brick.co.uk. Option 2: Incana WF Waterstruck brown multi clay pavers from Wienerberger; wienerberger.co.uk.
- 2. Granite to be supplied by CED stone, Essex, 01708 867 237,
- 3. Benches to be supplied by Streetlife or similar approved. streetlife.com | 020 30201509 | enquiriesUK@streetlife.com
- Ketley Clay Tiles: ketley-brick.co.uk | 01384 78361 | sales@ketley-brick.co.uk

**Revision History** 

Rev Date Detail - 19.02.24 JH Revised Design A 22.02.24 JH B 08.03.24 JH Draft Update

Draft tender



All dimensions and sizes to be verified by the Contractor on site. Any discrepancies to be verified with the Landscape Architect before work proceeds. No dimensions to be scaled from this drawing. Contractors must work to figured dimensions. © This drawing is subject to copyright of Roundfield, in accordance with our standard terms and conditions. Where an Ordnance Survey Drawing is shown on this drawing, it is re-produced under Crown copyright ©. All rights reserved.

The Old Church School Butts Hill Frome Somerset BA11 1HR

Westbury Town Council

**Drawing number** 

RF-110-300

Project/Location

Westbury Rotunda

Drawing title Hardworks Plan

**Drawing status** 

09.02.24

STAGE 4

1:50 @A1

Allowance made for refurbishment of step units, lowering of wall + new handrail, knee rail etc + tiled surfacing (refer to key)