

Refurbishment of Deneside Copse Play Park, Pennington, Lymington, Hampshire SO41 8JJ

Lymington & Pennington Town Council invites tenders from suitably experienced play equipment providers to refurbish an existing play area.

Please quote for the supply & installation of play equipment based on the following:

- All existing pieces of equipment to be removed from the site completely, not just cut off at the bases, and any existing play equipment stubs buried to be removed as well.
- The 2 yellow swing protector fences to remain (if swings are nearby) and be repainted yellow
- Design to include a minimum of the following: 2 multi-play units (with incorporated slides) one for ages 2-8 and another for ages 8+, toddler swings and flat swings, a 4 seater roundabout, a birds nest swing, rope/cobra swing and other innovative and challenging equipment.
- Age group is 2-12 years and to be where possible inclusive of ages, disability & mobility – with sensory and visual aids, if possible.
- Play equipment preferably to be metalwork, in a vibrant colour scheme
- In order to obtain maximum play pieces on the site, the existing wet pour matting positions could be utilised, to save digging out new ones
- Playground Wet pour is the preferred surfacing
- Location of any slide should be east or north facing so as to avoid being hot in summer
- The site to be zoned with play equipment by age of children so as to segregate toddlers and youths
- A new vehicle access gate and two new pro-safe soft close entrance gates to be installed – to replace the existing gates in situ
- No benches or additional waste bins required
- 2 new signs to be incorporated by each pedestrian gate and installed on the existing bow top fencing. Details to be supplied.
- The site is surrounded by residential properties, so no outdoor musical instruments or play equipment that is higher than 3m
- Welfare facilities to be located within the playground or at an agreed location with the Town Council (so as to keep the car parking for the houses clear)
- The existing bow top galvanised steel fencing surrounding the play park is to remain, as still in full working order
- A site visit is recommended prior to tender
- The available budget is £45,000
- Inspection costs not to be included in the quote – as this will be carried out by our own independent play inspector

Additional inclusions within quote

- Proposed method statement
- Proposed program of works
- Plans & illustrations showing design proposal
- Break down of each piece of equipment by cost
- Supplier's lead time
- Removal of all the existing play equipment and installation cost included
- Protective compound fencing while the works are carried out and a means of storing building equipment securely
- To include carriage

Submission of Design and Tender

- The designs and tender should be submitted to the council offices by **17.00 on Monday 7 May 2018.**

Site is located at Deneside Copse, Pennington, Lymington,
Hampshire, SO41 8JJ

Photos of the site - existing

