

TENDER ADDENDUM SHEET

Job No:	2642C
Client:	Blackpool & The Fylde College
Job Title:	FFFC - Groundworks & Service Infrastructure Scheme
Issue No.	2
Issue date	09.09.15

Ref	Query / Comment	Answer
2.1	Is the GRP switchroom enclosure to be supplied and fitted complete with the electrical gear already installed within it, or is the GRP enclosure and electrical gear supplied separately? Or does this not matter i.e. Contractors choice?	The GRP enclosure shall be supplied separate to the electrical switchgear and comes c/w plywood backboard. All internal electrical DB/ accessories will be supplied/fitted by the electrical contractor once the enclosure has been fixed.
2.2	"Please could you clarify item 3.2 e - Am I allowing 63mm water main from incoming water main point to support accommodation in the nearest spot only or am I allowing one feed right round the site (drawing ref 014.104.B.101)"	Allow for 3No 63mm MDPE incoming water connections to support accommodation as per drawing 014.104.M.101 T1. An empty 150mm water duct runs round the site for any future water supplies required.
2.3	Is the contractor to allow for removing the brick built kiosk?	Yes the contractor should allow for demolition of the existing brick switchroom enclosure and base prior to supply and installation of the new GRP enclosure and concrete base.
2.4	Clarify who is to be responsible for removing any existing cabins and various piles of rubbish / debris and fly tipped items within the works area.	The College will ensure existing redundant cabins / waste etc that are obstructing the works area are cleared prior to contractors starting on site.