

External wall to be lined in accordance with details shown on drawing 510.

Generally all bedrooms to have the external walls lined.

Bathrooms and staircases to remain as existing.

Following removal of screed supply and installed Ardex SD-T B Rapid drying Industrial Base Mix so

New underfloor heating installed to M&E consultant's specification.

Supply and install latex floor covering as specification.

New floor finishes.
New skirting throughout to match existing.

throughout all residential blocks.



Diagram illustrating the roof assembly components and their installation:

- New insulated tie rod to balcony roof.
- NI Insulation level to be down to and cutting parapet detail.
- NI Non-wooded
- New GFR tip to penetrate at roof to match the color of the existing fascia.
- NI
- Galv

IN EVERY BAY WINDOW
Supply and install as part of the window packages an insulated powder coated aluminum capping as part of the window package
To prevent cold bridge of structure

IN EVERY BAY WINDOW
Supply and install as part of the window package an insulated powder coated aluminum capping as part of the window package.
To prevent cold bridge of structure.

IN EVERY BAY WINDOW
Supply and install as part of the window package an insulated powder coated aluminum cladding as part of the window package
To prevent cold bridge of structure

8

| | | |
|----------|----------|--------|
| Scale: | Date: | Drawn: |
| 1:50@A0 | OCT 2023 | SD |
| Project: | DRG NO: | REV: |

PROPOSED 2F + ROOF PLAN

Scale: _____ Date: _____ Drawn: _____

| | | |
|----------|---------|------|
| Project: | DRG NO: | REV: |
|----------|---------|------|

2211-DA-00-DR-A-313_T2

NOT BE REPRODUCED WITHOUT PRIOR APPROVAL OF DEVONSHIRE ARCHITECTS

ALL DIMENSIONS MUST BE CHECKED ON SITE

ALL SETTING, LOCATIONS, BE OBTAINED ON SITE
THIS DRAWING MUST NOT BE USED FOR CONSTRUCTION UNLESS ISSUED FOR CONSTRUCTION
IF THERE IS ANY DOUBT ENQUIRE WITH THE AUTHOR