

**Specification for Works to Mountbatten Park Roadway and Pathway,
Queen's Ride, North Baddesley, Southampton SO52 9GT**

- Provide RAMS for works.
- All management for works
- Provide Welfare
- Provide CDM signage as required.
- Relay kerbs along both sides of the road from the cobbles to the scout hut
- Form a carpark 22m x 24m in size kerb and prepare subbase. Curbs to be re-laid along the length.
- Raise existing iron works on road.
- Regulate and base course the road and carpark 70mm thick as required.
- Lay 30mm SMA on the carpark (carpark is 1136 square mtrs in size) and 50mm of SMA on the existing road (roadway surface is 612 square mtrs) following application of a tack coat.
- Replace existing height barrier and relocate.
- Repair and resurface the adjacent footpath as required following the kerb breakout.
- Clean out existing road gullies.
- White lining of the car park and road as required.
- All concrete arisings to be mucked away – soil and mulch will be left adjacent to the road in the woods.

Exclusions/clarifications– .

- It is assumed no services will be present although a line search will be completed prestart.
- Time allowed 4 weeks.
- NBPC will notify residents/stakeholders in advance.
- The road will need to be closed for 4 weeks – pedestrian access only.
- No grass seeding allowed for.
- All permissions related to highways, trees or local authority will be sought by NBPC.