



Existing stone coping blocks are to be removed to allow lead flashings to be replaced. The copings are to be replaced using stainless steel restraint angles in the joints as per SE detail



The eaves overhang soffit is to be removed and the soffit is to be boarded with 18mm T & G boards, painted black



The gable end roof overhang is to be under-boarded using 18mm T & G boards painted black and an under-cloak board is to be provided under the overhanging edge tiles to allow pointing to the tile edge



Project: Lymm Village Hall
Client: Lymm Parish Council

Address: 5 Pepper Street, Lymm, WA13 0JB

Title: Main Hall Roof– Proposed External Roof Works-Front Elevation (South Facing)

Sketch Number: 19-8550-05A

PRINT @ A3 SIZE