

## **10032: GEDLING BOROUGH COUNCIL** **Arnold, Front Street (Eagle Square) Performance Area**

### **8. Works Activity Schedule**

The lump sum prices entered for each activity includes for all work and other things necessary to complete them.

<b>No</b>	<b>Description</b>	<b>Unit</b>	<b>Price (£)</b>
1	Mobilise and site set up ( <i>it is expected that a site compound area will be provided within a nearby area to be assigned by Gedling Borough Council. Size and location is yet to be confirmed</i> ) Item to include all necessary site fencing and pedestrian and vehicular traffic management.	Sum	
2	Maintain site set up for 6 weeks	Sum	
3	Site supervision and management for 6 weeks including all Health and Safety requirements.	Sum	
4	Demobilise site set up	Sum	
5	Arrangement and submission of all necessary NRSWA notices to the highway authority including required fees to enable the works to be undertaken. This activity will also include for liaison with the highway authority of Nottinghamshire County Council.	Sum	
6	Removal and disposal of a 4No existing mature trees and other shrubs from the existing planter at the front of No's 15 to 19 Front Street including removal and disposal of all topsoil within the planter.	Sum	
7	The demolition of an existing planter at the front of No's 15 to 19 Front Street including removal and disposal of all topsoil within the planter. The existing planter measures approximately 25m long by an average 10m wide and 1.5m high. It is constructed of Class A Engineering (Blue) brickwork estimated to be 225mm (1 brick) thick and includes a curved seating area created from the same brickwork and coping stones.	Sum	
8	The demolition of an existing seat outside No's 2 to 16 Front Street measuring approximately 8m long (curved) by 0.75m wide and 0.8m high constructed of Class A Engineering (Blue) brickwork. (optional)	Sum	
9	The construction of a new circular shaped planter at the front of No 19 Front Street in the same brickwork and to the same height as the existing one demolished. The planter will also include the filling with good quality topsoil, and planting of a new mature tree and shrubs.	Sum	
10	The paving of the area left by the demolition of the large planter at the front of No's 15 to 19 Front Street in block paving to match the existing paving (Marshals Mistral Silver Grey) around the demolished planter and to levels to blend in with the surrounding existing paving. Estimated area of paving required is approximately 170m <sup>2</sup> .	Sum	
11	The paving of the area to complete the pattern of the 'Eagle' in the area left by the removal of the existing seating adjacent to the existing planter with coloured clay block pavers.	Sum	
12	The paving to continue the kerb edge and blue clay paved channel around the circular paved area containing the 'Eagle'.	Sum	
13	The paving of the area left by the demolition of the seat outside No's 2 to 16 Front Street in block paving (Marshals Mistral Silver Grey) to match the existing paving around the demolished seat to levels to blend in with the surrounding existing paving.	Sum	
14	The provision and installation of 4No new seats (type Broxap Welburn) along the northern edge of the new paved area at the front of No's 15 to 19 Front Street.	Sum	
15	The provision and installation of a new seat (type Broxap Curved Welburn) around the eastern edge of the new paved area outside No's 2 to 16 Front Street. (Optional)	Sum	
16	The provision and installation of 3No new planters (type Gardenista Versailles or similar approved) containing mature trees along the northern edge of the new paved area at the front of No's 15 to 19 Front Street.	Sum	
		Total	

