

685_08_Internal Finishes Schedule (Rev. A)

Project title	Fairmile Cemetery, Henley	Project No	685
Compiled by	MHi	date	22/02/2019
Rev. A	RS	date	20/06/2019

Building: Chapel
FINISHES
Floor
Existing tiled floor retained, swept to remove any loose dirt and carefully cleaned with warm soapy water. No wire brush or abrasive application, no bleach or chemical cleaning product. Must use clean water.
Ceilings
Existing roof timbers and soffits between rafters cleaned.
Internal Walls
Damp and blown render to be removed and allowed to dry out. Replace with 2.5:1 local aggregate:lime putty render (Rev. A) with hand formed arises to be applied and finished with 3 coats of Heritage Lime lime wall wash with colour and finish to match existing.
Existing unaffected lime washed walls carefully cleaned with 2 coats of Heritage Lime wall wash with colour and finish to match existing.
https://www.rainguard.co.uk/downpipes/cast-iron-downpipes/ https://www.heritage-lime.com/products/limewash-products/
Joinery
All joinery formed with softwood frame, lined with 18mm WBP plywood and covered in a polished ash veneer. Refer to submitted drawings for further joinery details.
Rainwater Goods
All new rainwater goods and fixings are to be supplied by Yeoman and made of cast iron with a suitable black paint finish. Gutters are to use an MOG 150x100mm profile and fixed using rise and fall gutter brackets with square 75x75mm downpipes.
Where external fixings of rainwater goods are required, minor lime mortar repairs may also be required using an approximate mix of 2.5:1 local aggregate:lime putty.
https://www.rainguard.co.uk/guttering/cast-iron-guttering/ https://www.rainguard.co.uk/downpipes/cast-iron-downpipes/