3.5m wide access track. Where there is existing stable granular surface, existing sub-base to be retained. Otherwise allow for 200mm new type 1 base topped with 50mm, to follow existing levels with max. To fill dip, max. increase in level above existing: 100mm

Existing path - scrape up to 50m from existing surface, supply and lay 50-75mm self binding path gravel to join with existing improved section to the east

RIVER SOMER

P/R FENCE HT 1.2m

IL 79.25
+D 500ø

CONCRETE HEADWALL
I/R FENCE HT 1.0m

PO
CB

RAMP

IC
CL 82.21

GATE

IL 80.64

Improved riverside path.
Part of Phase 1.1
(refer to MSN656/Drg03)

Existing concrete surface retained

CTG
TP

Make good any disturbed grass to either side

Limit of working area (red line)

GRASS

3.5m

S2

TARMAC

Break out small area of existing macadam

Replace one damaged mesh panel approx. here, with spare one from dismantled section of fence.

Additional width to existing granular track making a total width of 3.5m

GRASS

GRAVEL

3.50

82.00

Existing fence retained

MH
CL 82.28

New bollards, including 2no. removable and lockable.

Section of existing fence removed

Existing post replaced with re-used corner post

W/M FENCE HT 2.0m

Existing post

GRASS

MHs
CL 82.31

Existing granular track retained, but 50mm of surface scraped off and replaced with buff self binding gravel

IC
CL 82.09

SVP

GATE

TARMAC

New alignment for fence to Somer Center garden

Existing fence retained

SOMER CENTRE GARDEN

GRASS

GRASS

MHs
CL 82.31

PAVING

EAVES 85.40

CBs

FOOTPATH (TARMAC)

SOMER CENTRE

TARMAC

TARMAC

DCH

MHs
CL 82.32

S1

L.BIN

GRASS

LP

C A R P A R K

EAVES 85.33

5 4 3 2 1 0 5 10 15m

N
NORTH

new Leaf STUDIO
CHARTERED LANDSCAPE ARCHITECTS

Client: Midsomer Norton Town Council

Project: **Town Park - Phase 1.2**

Title: West Entrance - Interim Works

Drg by: ADFK | Date: 04/2019 | Scale: 1:200 @ A3

Chkd by: | Drg No: **MSN656/Drg14** | Rev:

1.17 PAINTWORKS, BATH ROAD, BRISTOL BS4 3EH Tel: 0117 300 5330