



CAMELFORD TOWN COUNCIL

RIVERBANK SPECIFICATION

It is anticipated that these works will take 11 days to complete and to start in the Spring/Summer 2021 when river flows are more manageable and at the end of the fisheries spawning and migration period.

There are 2 sections of riverbank that need repair. The first section (up to Broadwood Bridge) is approximately 41m. This section already has rock rolls installed held in place with pins and rope. The second section (from the bridge to the bend in the river) is approximately 80m. Some parts of this section have rock rolls but most of this section is without and eroding badly. Works to include Environment Agency FRAP licence administration and licence fees, establishment of people and plant, and excavation and disposal off site to suitably licenced tip.

1. Section 1 (Patching work):

- Supply and placement of rock rolls or coir rolls (varying depths of between 1m and 2m in height) to existing roll rock installation and fill with suitable imported material to rear of raised existing rock roll (41m). Installation (where applicable) of short wire ground anchors. Grade finished riverbank levels and apply grass seed and make good all areas disturbed by works.

2. Section 2 (New):

- Supply and placement of rock rolls or coir rolls of varying heights between 1m and 2m in height along length of riverbank.
- Grade finished riverbank levels and apply grass seed and make good all areas disturbed by works.

Site visits are encouraged to understand fully the scope of works.