

Item	Description	Quantity	Unit	Rate	£ p
	<b><u>River Bank Stabilisation</u></b>				
A	Regrade existing bank to form even levels and grade to receive rock mattresses	1	item		
B	Provide and place rock mattresses along river bank and fix in place with chestnut stakes and tie back chord fixed in river bank.  Approx 38 lin m	1	item		
C	Break out defective footpath, excavate for new footpath load and cart away arisings	122	m2		
D	Provide and lay  160mm thick bed of Type 1 crushed graded stone  20mm dense binder course to a thickness of 50mm  6mm dense surface course to a thickness of 20mm	122	m2		
E	Trim out for, provide and lay 50 x 150mm precast concrete edgings bedded on and haunched at rear in concrete	74	m		
F	Provide and lay 150mm thick bed of topsoil in making good to river bank and sow grass seed	1	item		
G	Remove dead trees and clear away  Provide and plant new trees species to be agreed	3	nr		
H	Allow for setting up temporary compound and remove upon completion	1	item		
I	Allow temporary works in diverting river away from works if required  PROVISIONAL	1	item		
J	Allow for design fees and obtaining permissions  PROVISIONAL	1	item		

Print Summary

£ p

Bill 1 River Bank Stabilisation Newark

Total :