
Clancy

2.1

C PERFECT



Clancy Consulting 2020

2.3

2.2

6.0 Structural Proposals



>		
anc	nsulting "	
С С	8	
_	2	

Job No.: 2/10838 Rev[.] 00




Figure 5



Figure 6 – Photo of jack within maintenance pit. Photo taken by CCL during site visit.

According to the Arup drawings, the secondary steelwork is founded on 400xmm x 400mm x 105mm high concrete plinths on a 300mm thick ground bearing stab reinforced with 12mm diameter reinforcement at 200mm centres top and bottom. The as-built information does not prescribe an allowable ground bearing pressure. 2.7



Figure 7 – Section showing support of maintenance pit columns extracted from Arup drawings

Lateral stability of the suspended ground floor structure is understood to be provided by 60.3 x 4 CHS bracing elements provided vertically. The precast planks may also be providing stability to the frame by providing horizontal 'floor plate' action. 2.8

Page 9 of 22 West Ham Bus Garage East Wing RIBA Work Stage 1 Feasibility Report - Doc Rev. 00

Clancy Consulting 2020



Loading Assessment for Proposed Maintenance Pit Infill

Job No.: 2/10838 Rev: 00

Loading Assessment Methodology

3.0

- and proposed loading from the proposed infill of the maintenance pit and the racking loads. The purpose of this is to highlight, at a high-level, where infill proposals may cause possible increases in loading beyond the existing and as such strengthening and / or further investigation works may As part of our feasibility study, we have undertaken a loading assessment to compare the existing be required to justify structure. 3.1
- CCL have not been provided with the racking loads and so we have made assumptions as to the proposed live load requirements that will be imposed by the storage of the lost and found items. 3.2
- member sizes and their capacities for the proposed infil loading. However, the Arup drawings do not confirm the bearing capacity of the soil under the ground bearing slab. Furthermore, even though the jacks (see Figure 6) within the maintenance pits are rated to 20 tonnes, and the be compared with proposed loads. As such, we have chosen to undertake an assessment of the existing loading on the foundation to not include the loading from the jacks and which, in our The Arup as-built drawings within the health and safety file have allowed us to confirm the structural the load combinations showing the simultaneously acting jacking load and the imposed load that the foundations have been designed for, we are not able to confirm that the foundation slab structure has been designed for the full jacking load when assessing the existing loads that are to foundations may have been designed to accommodate this load to some extent, without confirming opinion, is conservative. 3.3
- Based on the above, the load assessment for the proposed infill works will check the following: -3.4

a) Check on the existing steel members with proposed loading - we are of the opinion that a check on the 203 UC 46 beams is sufficient.

b) Comparison on assumed existing loading on foundation slab with proposed loading. **Existing Foundation Loading Assessment**

- According to Arup drawing 121437-S431-C2 (see Appendix A), the existing suspended ground floor is designed for an imposed live loading of 7.5kN/m² 3.5
- Existing applied loads are as follows: -3.6



3.7

Possible Savings in Structural Capacity due to Proposed Loading

115,000 items were found across the TfL network during 2020. As such, the density and weights of stored items do differ – see Figure 8. Due to the change in use from bus imposed loads to storage mobile phones, documents, etc. According to the TfL Lost Property Office transparency data (https://content.tfl.gov.uk/lost-property-office-transparency-data-fy-2019-20-21.pdf), approximately of lost and found property items, we would assume [to be confirmed by TfL] a reduced live load The composition of the lost and found items is expected to vary significantly, from bags, jewellery, 3.8

Page 10 of 22 West Ham Bus Garage East Wing RIBA Work Stage 1 Feasibility Report - Doc Rev. 00

Clancy Consulting 2020

6.0 Structural Proposals





Job No.: 2/10838 Rev: 00 allowance of 5.0kN/m² is adequate on the existing floor slabs. Therefore, there is a minimum additional 2.5kN/m² capacity within the existing structure to accommodate overall load changes.



Figure 8 – Photo from within a TfL Lost Property Office showing the storage of lost property riems (source: https://ondonist.com/bondontransport/fris-annous-lost-property-office-is-moving-tosouth-ensington) 3.9 Furthermore, as the original structure was designed to British Standards, additional capacity in the structure can be found by assessing proposals with Eurocodes load factors. See below a comparison of the load factors between the two standards.

British Standards 1.4 Enrocodes 1.35	<u>Dead Load</u> 1.4 1 उरु	Live Load 1.6 1.5
		0.

3.10 The load increase from the proposed works will be calculated assuming 5kN/m² live load on the existing structure as well as the on the proposed infill. The dead load from the proposed infill will also be accounted for in the load comparison. Furthermore, we have allowed for an additional 0.15kN/m² nominal services loading on the infill.

4.0 Options for Infilling Maintenance Pit Openings

- 4.1 The proposed potential infiling options have been proposed based on the following criteria: Top level of the new infil slab can be made to match the existing suspended floor slab with minimum modification to the existing structure such that a flush finish can be achieved to
 - minimum modification to the existing structure such that a flush finish can be achieved to a childrate transfer of trolleys, etc. Deletisious linkthusing theor construction to not concluded existing structure and foundations
- Relatively lightweight floor construction to not overload existing structure and foundations.
 Capable of supporting proposed 5kN/m² live load from the lost and found property items that are to be stored.
 - Ease of installation.
- 4.2 Pros and cons are listed for each of the options. We have not undertaken a costing exercise for the options.

C clancy consulting

Jab No.: 2/10838 Rev: 00

Option 1 – Composite Metal Deck



4.3 This option proposes the use of a composite metal deck across the opening that is supported of the existing PFC at the edge of the maintenance pit opening. The composite deck is composed of a 0.9mm thick corrugated steel profile of which is filled with concrete hat can be power floated to achieve a flush finish with the existing flooring. The concrete will be reinforced with a A193 mesh.

Pros and Cons

Pros

No temporary works needed for installation of composite deck as the steel work will effectively be the formwork.

Concrete can be power floated to achieve a flush finish and so no additional screed is required.

Simple reinforcement arrangement.

Quick installation, all deck can be laid, and concrete poured in one go (subject to access constraints for concreting)

Weight of the 0.9mm thick 900mm wide x 1250mm long steel component is approx. 10kg and so lends itself to being easily handled around site.

Flexible slab depth that can vary from 120mm thick to 200mm thick and so there is more flexibility in working around the existing structural elements to achieve floor levels.

Openings up to 300mm square for services etc. can be introduced with no additional reinforcement requirements.

Can achieve a minimum 60-minute fire rating without modification.

Cons No significant disadvantages for this option.

Load Assessment - Check capacity of 203 UC 46

4.4 The 203 UC 46 was assessed as capable of supporting the proposed infill and the existing infill with the 5kNm² imposed loading. As such, this option would be possible without any strengthening of the existing steelwork. West Ham Bus Garage East Wing RIBA Work Stage 1 Feasibility Report - Doc Rev. 00 Page 12 of 22

© Clancy Consulting 2020

Page 11 of 22

West Ham Bus Garage East Wing RIBA Work Stage 1 Feasibility Report - Doc Rev. 00

Clancy Consulting 2020