

Invitation to Tender – Wroughton Parish Council Tree Works – Appendix A

Area	Tree ref no	Tree type	Timescale (months)	Work required
Belmont Green North Wroughton	T67	Mountain Ash	6	Sever/ remove ivy
	T97	Common Oak	6	Sever/ remove ivy
	T108	Common Ash	6	Fell to ground level
	T109	Common Ash	6	Reinspect to monitor condition
	T1	Wild cherry	12	Fell to ground level
	T87	Lawson Cypress	12	Fell to ground level
	T91	Common Hornbeam Hawthorn	12	Remove epicormic growths and remove adjacent hawthorn which is growing into crown
	T92	Common Hornbeam	12	Remove epicormic growths
	T99	Common Hornbeam	12	Sever/ remove ivy Remove epicormic growths
Beranburh Play Area	T1	Common Ash	6	Reinspect
	T2	Common Ash	6	Remove major dead wood
	T8	Common Ash	6	Remove major dead wood
	T11	Common Ash	6	Remove epicormic growth Remove major dead wood
	T16	Wild Cherry	6	Remove blue rope from south side stem at 3m to prevent further girdling
	T29	Common Ash	6	Remove major dead wood Remove 1 st major limb, south side of stem at 2m
	T31	Common Ash	6	Remove major dead wood
	T32	Common Ash	6	Reinspect
	T33	Common Ash	6	Reinspect
	T34	Common Ash	6	Fell & remove stumps
	T27	Bird Cherry	12	Raise low canopy to 2m
	T28	Common Ash	12	Raise low canopy to 2m Remove sucker growth
	T30	Bird Cherry	12	Raise low canopy to 2m
Central Wroughton & Weir Field	T8	Common Laburnum	6	Sever/ remove ivy
	T129	Common Ash	6	Sever/ remove ivy
	T130	Common Ash	6	Sever/ remove ivy
	T136	Common Ash	6	Sever/ remove ivy Remove major dead wood
	T137	Sycamore	6	Sever/ remove ivy
	T139	Common Ash	6	Sever/ remove ivy
	T140	Common Ash	6	Remove major dead wood
	T145	Common Ash	6	Fell to ground

	T146	Sycamore	6	Reduce stem on fence side, overhanging private garden. Reduce by 2-3m to reduce risk of union failure.
	T151	Common Ash	6	Fell to ground level
	T156	Common Ash	6	Fell
	T157	Common Ash	6	Sever/ remove ivy
	T162	Common Ash	6	Fell to ground level
	T163	Weeping Willow	6	Reduce crown by 25%
	T165	Weeping Willow	6	Remove major dead wood
	T172	Silver Maple	6	Cut back growth from site/ fence/ roadway to 5m height
	T193	London Plane	6	End weight reduction by 20% to major limb, west side of crown
	T199	Common Horse Chestnut	6	Reduce crown by 25% to reduce forces on tight unions
	T204	Sycamore	6	End weight reduction to limb growing over road
	T209	Bastard Service Tree	6	Fell
	T226	A group	6	Fell middle tree in group of 3(poor union & weak stem)
	T131	Common Ash	By next inspection	Sever/ remove ivy
	T132	Sycamore		Sever/ remove ivy
	T133	Sycamore		Sever/ remove ivy
	T134	Sycamore		Sever/ remove ivy
	T147	Sycamore		Sever/ remove ivy
	T208	Black Cherry		Crown Cleaning to improve appearance
	T212	Common Horse Chestnut		Sever/ remove ivy
	T220	Sycamore		Sever/ remove ivy
Maunsell Way Playing Fields Area	New G1	Hedgerow to west boundary of open space	6	Remove multiple dead elm from hedge
	T44	Crack Willow	6	Re-pollard
	T45	Crack Willow	6	Re-pollard
	T46	Crack Willow	6	Re-pollard
	T47	Crack Willow	6	Re-pollard
	T50	Crack Willow	6	Re-pollard
	T51	Crack Willow	6	Re-pollard
	T52	Crack Willow	6	Re-pollard
	T53	Crack Willow	6	Re-pollard Sever/ remove ivy
	T55	Crack Willow	6	Re-pollard
	T57	Crack Willow	6	Re-pollard
	T58	Crack Willow	6	Re-pollard Sever/ remove ivy
	T59	Crack Willow	6	Re-pollard

	T60	Common Ash	6	Re-inspect
	T61	Crack Willow	6	Re-pollard
	T63	Common Ash	12	Sever/ remove ivy
	T64	Common Ash	12	Sever/ remove ivy
	T35	Western Balsam Poplar	By next inspection	Sever/ remove ivy Remove major dead wood