



1.0 Tender Document

Market Deeping Town Council wish for companies to quote on the replacement of safety surfacing to include engineering drainage solutions to existing playground equipment currently installed at the John Eve Park, Market Deeping. The need has arisen due to usage and previous works not being able to withstand the inclement weather. Companies are asked to supply prices based upon the lots enclosed and the chosen contractor will be awarded the contract as a whole or partial depending on the Councils deliberations.



Tender Solutions and Offers should be returned by the following address by noon on the Monday 10th August 2020.



Market Deeping Town Council
Town Hall, Market Place, Market Deeping, Peterborough PE6 8EA

Telephone 01778 343170

Return Address :-

Market Deeping Town Council, Town Hall, Market Place, Market Deeping, Peterborough PE6 8EA

Addressee :-

Mrs Sarah Lydford, Market Deeping Town Council Clerk

Technical Enquires :-

Mdtc.townclerk@btconnect.com

Market Deeping Town Council will endeavour return technical enquiries within 72hrs of receiving the requests. Face-to-face meetings can be arranged using Socially Distanced methods within the first seven working days of the tender being published.



2.0 Lot 1 – Teacup Roundabout – Full surface uplift, removal, and replacement.

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.	<p>Item rate and price</p>
---	--	----------------------------

Additional Notes relating to Lot 1:-



3.0 Lot 2 – Cobra Seesaw – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.	<p>Item rate and price</p>
---	--	----------------------------

Additional Notes:-



4.0 Lot 3 – Spiro Whirl Roundabout – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.	<p>Item rate and price</p>
---	--	----------------------------

Additional Notes:-



5.0 Lot 4 – Combination Swing – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.	<p>Item rate and price</p>
---	--	----------------------------

Additional Notes:-



6.0 Lot 5 – Mystical World Multiplay – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.	<p>Item rate and price</p>
---	--	----------------------------

Additional Notes:-



7.0 Lot 6 – Hurricane Swing – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Excavation - 200mm deep excavation into soil including all plant hire and removal from site.• Stone - 200mm deep MOT Type 1 granite supplied and compacted to 75mm to form free draining foundation for wetpour surfacing• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.• Mulch impact surfacing consisting bonded coated recycled rubber mulch	<p>Item rate and price</p>
---	---	----------------------------

Additional Notes:-



7.0 Lot 7 – Pendulum Swing – Full surface uplift, removal, and replacement

	<p>Brief Of Works</p> <ul style="list-style-type: none">• Removal of Wetpour / Tiles / Carpet / Rubber Mulch per m2. (Including disposal of waste)• Excavation - 200mm deep excavation into soil including all plant hire and removal from site.• Stone - 200mm deep MOT Type 1 granite supplied and compacted to 75mm to form free draining foundation for wetpour surfacing• Wetpour impact surfacing consisting of SBR base layer and a 20mm EPDM wearing course.• Mulch impact surfacing consisting bonded coated recycled rubber mulch	<p>Item rate and price</p>
---	---	----------------------------

Additional Notes:-



8.0 Additional Consultation Elements to be considered

	Site Set Up & Preliminaries	
Yes / No	Description of works elements needed to be complied with prior to work being started	Costs & Notes
	To carry out site set up and preliminaries including setting up area and marking up site for installation.	
	To prepare and submit Risk Assessments and Method Statements covering maintenance works to client hand over. - Small Projects.	
	To supply staff welfare facilities whilst working on site as required under the Workplace (Health, Safety and Welfare Act) Regulations 1992	
	To hire, erect and remove Fencing per panel including block feet and clips - per panel (3.5m). Please give full details of the Fencing including the method(s) of securing the site during the works phase.	
	Return to site and collect security fencing once concrete foundations have cured / project is complete and make good any damage to soft areas of soil.	



Market Deeping Town Council
Town Hall, Market Place, Market Deeping, Peterborough PE6 8EA

Telephone 01778 343170

9.0 Supporting Documentation

Please supply any additional supporting material to aid the Market Deeping Town Council to review your submission. Market Deeping Town Council would like the supplier's proof of insurances and operative training certification enclosed in this section or referenced as an enclosed appendix.



Market Deeping Town Council
Town Hall, Market Place, Market Deeping, Peterborough PE6 8EA

Telephone 01778 343170

10.0 Terms & Conditions

Please include your standard Terms & Conditions Statements and detail the lead time to perform these lot(s).