

Qty	Unit	Description
		<b>REMOVALS</b>
		Remove and dispose of the following:
		1 No. Timber Single Tower Multiplay Unit (Cut off below ground level)
		1 No. 2 Place Timber Swing (Cut off below ground level)
		3 No. Timber Knee Rail Barriers (Cut off below ground level)
		1 No. 1.8m Cone Climber Post (Retain for Possible Refurbishment / Re-installation)
		1 No. Spinner (Retain for Possible Re-installation)
		1 No. Timber Triple Somersault Bars (Cut off below ground level)
1	Each	Regular skip 8yard skip
60	Sq. Mtr	50mm EPDM Wet pour
1	Each	Regular skip for rubber holds maximum of 100m2
60	Sq. Mtr	Regulate existing base where wet pour removed
		<b>EQUIPMENT</b>
1	Each	Esk Pike Multiplay Unit - Fort Theme
1	Each	2 Place 2.4m Olympic Swing - Yellow
1	Each	Mirage Inclusive Seat – Bright Colour
		<b>SURFACING</b>
60	Sq. Mtr	2.3m CFH (80mm) Black EPDM Wet pour (100+)
148	Sq. Mtr	0.8m CFH (20mm) Black EPDM Wet pour (100+)
		<b>OTHER</b>
1	Each	Delivery of above items
1	Each	Access and site reinstatement
1	Each	Post Installation Inspection
		<b>SITE WELFARE</b>
1	Each	Site Welfare and Management