

## **Swanage Town Council Resurfacing**

**27 October 2020**

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

## Table of Contents

Title	Page
A10 PROJECT PARTICULARS	3
A11 TENDER AND CONTRACT DOCUMENTS	4
A12 THE SITE/ EXISTING BUILDINGS	5
A13 DESCRIPTION OF THE WORK	7
A20 JCT MINOR WORK BUILDING CONTRACT (MW)	8
A30 TENDERING/ SUBLETTING/ SUPPLY	11
A31 PROVISION, CONTENT AND USE OF DOCUMENTS	13
A32 MANAGEMENT OF THE WORKS	17
A33 QUALITY STANDARDS/ CONTROL	20
A34 SECURITY/ SAFETY/ PROTECTION	25
A35 SPECIFIC LIMITATIONS ON METHOD/ SEQUENCE/ TIMING	30
A36 FACILITIES/ TEMPORARY WORK/ SERVICES	31
A37 OPERATION/ MAINTENANCE OF THE FINISHED WORKS	33
A40 CONTRACTOR'S GENERAL COST ITEMS: MANAGEMENT AND STAFF	34
A41 CONTRACTOR'S GENERAL COST ITEMS: SITE ACCOMMODATION	35
A43 CONTRACTOR'S GENERAL COST ITEMS: MECHANICAL PLANT	36
A44 CONTRACTOR'S GENERAL COST ITEMS: TEMPORARY WORKS	37
A54 PROVISIONAL WORK/ ITEMS	38

## A10 PROJECT PARTICULARS

### 110 THE PROJECT

- Name: Swanage Town Council.
- Nature: Resurfacing of Car Parks and Service Roads.
- Location: Main Beach Car Park: Victoria Avenue, Swanage, BH19 1PW  
North Beach Car Park: De Moulham Road, Swanage, BH19 1NL  
De Moulham Estate: De Moulham Road, Swanage, BH19 1PD  
Northbrook Road: Northbrook Road, Swanage BH19 1PS.
- Timescale for construction work: Completion by 26 March 2021.

### 120 EMPLOYER (CLIENT)

- Name: Swanage Town Council.
- Address: Town Hall, High Street, Swanage BH19 2NZ.
- Contact: Dr Martin Ayres.
- Telephone: 01929 423636.
- E-mail: m.ayres@swanage.gov.uk.

### 130 PRINCIPAL CONTRACTOR (CDM)

- Name: The Contractor.
- Address: To be confirmed.
- Contact: To be confirmed.
- Telephone: To be confirmed.
- E-mail: To be confirmed.

### 140 ARCHITECT/ CONTRACT ADMINISTRATOR

- Name: James Lee.
- Address: Dorset Property, Dorset Council, County Hall, Dorchester DT1 1XJ.
- Contact: James Lee.
- Telephone: 01305 221915.
- Email: james.lee@dorsetcouncil.gov.uk.

### 150 PRINCIPAL DESIGNER

- Name: James Lee.
- Address: Dorset Property, Dorset Council, County Hall, Dorchester DT1 1XJ.
- Contact: James Lee.
- Telephone: 01305 221915.
- E-mail: james.lee@dorsetcouncil.gov.uk.

## **A11 TENDER AND CONTRACT DOCUMENTS**

### **110 TENDER DRAWINGS**

- The tender drawings are: As drawing schedule .

### **120 CONTRACT DRAWINGS**

- The Contract Drawings: The same as the tender drawings.

### **160 PRECONSTRUCTION INFORMATION**

- Format: The Preconstruction information is described in these preliminaries in Section A34. It refers to information given elsewhere in the preliminaries and other tender documents.

## A12 THE SITE/ EXISTING BUILDINGS

### 110 THE SITE

- Description: All sites are within the proximity of Swanage.  
Main Beach Car Park: Public car park accessed from Victoria Avenue, Swanage.  
North Beach Car Park: Public car park, HM Coastguards headquarters and access to Swanage Town Football Club, accessed from De Moulham Road, Swanage.  
De Moulham Estate: Private properties accessed via Rabling Lane and service roads from De Moulham Road.  
Service Road off Northbrook Road: Private properties accessed from Northbrook Road..

### 120 EXISTING BUILDINGS ON/ ADJACENT TO THE SITE

- Description: Main Beach Car Park: Public toilet block located to the south boundary of the car park.  
North Beach Car Park: HM Coastguards headquarters and access to Swanage Town Football Club.  
De Moulham Estate: Various private properties accessed from proposed areas of resurfacing.  
Service Road off Northbrook Road: Various private properties accessed over proposed area of works..

### 180 HEALTH AND SAFETY FILE

- Availability for inspection: The Health and Safety File for the site/ building may be seen by appointment during normal office hours at: Where available health and safety files can be accessed by arrangement through Swanage Town Council. .
- Other documents: None.
- Arrangements for inspection: N/A.

### 200 ACCESS TO THE SITE

- Description: Keep the existing entrances and access routes for vehicular and pedestrian traffic free and safe for use at all times. Provide efficient watching and warning to the public and occupants of the movement of all vehicles in connection with the Works.

Do not drive vehicles over any surface not designed for vehicular traffic without adequately protecting the surface. Any surface damage is to be made good at the Contractor's expense. Access over soft landscaped areas will require a 'Method statement' from the Contractor. Deliver materials and plant etc. and remove excavated materials, rubbish etc. from the site in rubber-tyred barrows or the like.

Specific access arrangements to the site for the contract period is to be agreed prior to commencement of works..

- Limitations: As above.
- Access for inspections: Provide access at reasonable times for both on-site and off-site work.

### 210 PARKING

- Restrictions on parking of the Contractor's and employees' vehicles: Arrangements for the Contractor's designated compounds and parking areas to be agreed prior to commencement of works, to be enclosed within the car parks works areas..

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

220 USE OF THE SITE

- General: Do not use the site for any purpose other than carrying out the Works.
- Limitations: N/A.

230 SURROUNDING LAND/ BUILDING USES

- General: Adjacent or nearby uses or activities are as follows:
  - Main Beach Car Park: Public access to the area not outlined for resurfacing may need to be retained and for access and to house to the annual winter market.
  - North Beach Car Park: 24/7 access for HM Coastguards employees and public and staff access to Swanage Town Football Club should be retained.
  - De Moulham Estate: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period.
  - Service Road off Northbrook Road: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period..

250 SITE VISIT

- Assessment: Ascertain the nature of the site, access thereto and all local conditions and restrictions likely to affect the execution of the Works.
- Arrangements for visit: Site visits should be pre-arranged with the Occupiers Representative, at which time the Contractor should ascertain the nature of the site, access thereto and all local conditions and restrictions likely to affect the execution of the Works.  
Contact: Gail Percival. Tel: 01929 766034.

## **A13 DESCRIPTION OF THE WORK**

### **110 PREPARATORY WORK BY OTHERS**

- Details: N/A.
- Timescale: N/A.

### **120 THE WORKS**

- Description: Main Beach Car Park: Partial resurfacing of car park, drainage repairs, installation of public area electrical supply and re-lining.  
North Beach Car Park: Partial resurfacing of car park, weed treatment to localised areas and formation of tree enclosures and re-lining.  
De Moulham Estate: Resurfacing of 3nr. gravel service roads.  
Service Road off Northbrook Road: Tarmac patch repair..

### **130 WORK BY OTHERS CONCURRENT WITH THE CONTRACT**

- Description: N/A.

### **140 COMPLETION WORK BY OTHERS**

- Description: N/A.

## **A20 JCT MINOR WORK BUILDING CONTRACT (MW)**

### **JCT MINOR WORKS BUILDING CONTRACT**

- The Contract: JCT Minor Works Building Contract 2016 Edition.
- Requirement: Allow for the obligations, liabilities and services described.

### **THE RECITALS**

#### **First - THE WORKS AND THE CONTRACT ADMINISTRATOR**

- The work comprises: Main Beach Car Park: Partial resurfacing of car park, drainage repairs, installation of public area electrical supply and re-lining.  
North Beach Car Park: Partial resurfacing of car park, weed treatment to localised areas and formation of tree enclosures and re-lining.  
De Moulham Estate: Resurfacing of 3nr. gravel service roads.  
Service Road off Northbrook Road: Tarmac patch repair..
- Architect/ Contract Administrator: See clause A10/140.

#### **Second - CONTRACT DOCUMENTS**

- Contract drawings: As listed in clause A11/120.  
Contract documents: The following have been prepared which show and describe the work to be done A specification and Work schedules.

#### **Third - PRICED DOCUMENTS**

- Documents to be priced or provided by the Contractor: Work schedules.

### **ARTICLES**

#### **3 - ARCHITECT/ CONTRACT ADMINISTRATOR**

- Architect/ Contract Administrator: See clause A10/140.

#### **4 and 5 - PRINCIPAL DESIGNER/ PRINCIPAL CONTRACTOR**

- Principal Designer: See clause A10/150.
- Principal Contractor: See clause A10/130.

### **CONTRACT PARTICULARS**

#### **Fourth Recital and Schedule 2 - BASE DATE**

- Base date: 10 days before the date for return of tenders .

#### **Fourth Recital and clause 4.2 - CONSTRUCTION INDUSTRY SCHEME (CIS)**

- Employer at the Base Date is a 'contractor' for the purposes of the CIS.

#### **Fifth Recital - CDM REGULATIONS**

- The project is notifiable.

#### **Sixth Recital - FRAMEWORK AGREEMENT**

- Framework agreement: Does not apply.
- Details:
  - Date: Not Applicable.
  - Title: Not Applicable.
  - Parties: Not Applicable.



Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

Seventh Recital and Schedule 3 - SUPPLEMENTAL PROVISIONS

- Collaborative working: Supplemental Provision 1 applies.
- Health and safety: Supplemental Provision 2 applies.
- Cost savings and value improvements: Supplemental Provision 3 applies.
- Sustainable development and environmental considerations: Supplemental Provision 4 applies.
- Performance indicators and monitoring: Supplemental Provision 5 does not apply.
- Notification and negotiation of disputes: Supplemental Provision 6 applies. Where Supplemental Provision 6 applies, the respective nominees of the parties are:
  - Employer's nominee: James Lee.
  - Contractor's nominee: \_\_\_\_\_.Or such replacement as each party may notify to the other from time to time.

Article 7 - ARBITRATION

- Article 7 and Schedule 1 apply.

Clause 2.2 - COMMENCEMENT AND COMPLETION

- Works commencement date: Provisionally January 2021 .
- Date for Completion: 26th March 2021 .

Clause 2.8 - LIQUIDATED DAMAGES

- At the rate of £300 per calendar day.

Clause 2.10 - RECTIFICATION PERIOD

- Period: 12 months from the date of practical completion.

Clause 4.3 - INTERIM PAYMENTS

- Interim Valuation Dates:
  - The first Interim Valuation Date is: One month after the Works Commencement Date.
  - Thereafter at intervals of: monthly.
- Payments due prior to practical completion:
  - Percentage of total value of the work etc.: 95 per cent.
- Payments becoming due on or after practical completion:
  - Percentage of the total amount to be paid: 97½ per cent.

Clause 4.3 and 4.8 - FLUCTUATIONS PROVISION

- The following fluctuations provision applies: No fluctuations provision applies.
- Where Schedule 2 applies, the percentage addition (paragraph 13) is Not Applicable.

Clause 4.8.1 - SUPPLY OF DOCUMENTATION FOR COMPUTATION OF AMOUNT TO BE FINALLY CERTIFIED

- Period: Three months from the date of practical completion.

Clause 5.3 - CONTRACTOR'S PUBLIC LIABILITY INSURANCE - INJURY TO PERSONS OR PROPERTY

- The required level of cover for any one occurrence or series of occurrences arising out of one event:
  - Not less than: £10,000,000.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

Clauses 5.4A, 5.4B and 5.4C - INSURANCE OF THE WORKS, ETC. - ALTERNATIVE PROVISIONS

- Clause 5.4B applies.
- Where clause 5.4A or 5.4B applies, percentage to cover professional fees: 15 per cent.
- Where clause 5.4C applies, insurance arrangements - details of the required policy or policies: Not Applicable.

Clause 7.2 - ADJUDICATION

- The Adjudicator is: To be advised.
- Nominating body: Royal Institute of British Architects.

Schedule 1 paragraph 2.1 - ARBITRATION

- Appointor of Arbitrator (and of any replacement): President or a Vice president of the: Royal Institute of British Architects.

**THE CONDITIONS**

SECTION 1: DEFINITIONS AND INTERPRETATION

1.8 - APPLICABLE LAW

- Amendments: None.

SECTION 2: CARRYING OUT THE WORKS

SECTION 3: CONTROL OF THE WORKS

SECTION 4: PAYMENT

SECTION 5: INJURY, DAMAGE AND INSURANCE

SECTION 6: TERMINATION

SECTION 7: SETTLEMENT OF DISPUTES

EXECUTION

- The Contract: Will be executed as a deed.

CONTRACT GUARANTEE BOND

- Contract Guarantee Bond: Not Applicable.

JCT PUBLIC SECTOR SUPPLEMENT

- Document: The JCT Public Sector Supplement 2011 - Fair Payment, Transparency and Building Information Modelling.
- Fair Payment provisions Do not apply.
- Transparency provisions Do not apply.
- Building information modelling provisions Do not apply.

## **A30 TENDERING/ SUBLETTING/ SUPPLY**

### **MAIN CONTRACT TENDERING**

- 110 SCOPE
- General: These conditions are supplementary to those stated in the Invitation to Tender and on the form of tender.
- 145 TENDERING PROCEDURE
- General: In accordance with NBS Guide to Tendering for Construction Projects.
  - Errors: Alternative 1 is to apply.
- 160 EXCLUSIONS
- Inability to tender: Immediately inform if any parts of the work as defined in the tender documents cannot be tendered.
  - Relevant parts of the work: Define those parts, stating reasons for the inability to tender.
- 170 ACCEPTANCE OF TENDER
- Acceptance: No guarantee is offered that any tender will be recommended for acceptance or be accepted, or that reasons for non acceptance will be given.
  - Costs: No liability is accepted for any cost incurred in the preparation of any tender.
- 190 PERIOD OF VALIDITY
- Period: After submission or lodgement, keep tender open for consideration (unless previously withdrawn) for not less than 90 days.
  - Date for possession/ commencement: See section A20.

### **PRICING/ SUBMISSION OF DOCUMENTS**

- 210 PRELIMINARIES IN THE SPECIFICATION
- The Preliminaries/ General conditions sections (A10-A56 inclusive) must not be relied on as complying with SMM7/ NRM2.
- 250 PRICED DOCUMENTS
- Alterations: Do not alter or qualify the priced documents without written consent. Tenders containing unauthorised alterations or qualifications may be rejected.
  - Measurements: Where not stated, ascertain from the drawings.
  - Deemed included: Costs relating to items, which are not priced, will be deemed to have been included elsewhere in the tender.
  - Submit: Within one week of request.
- 310 TENDER
- General: Tenders must include for all work shown or described in the tender documents as a whole or clearly apparent as being necessary for the complete and proper execution of the Works.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 550 HEALTH AND SAFETY INFORMATION

- Content: Describe the organization and resources to safeguard the health and safety of operatives, including those of subcontractors, and of any person whom the Works may affect.
- Include:
  - A copy of the health and safety policy document, including risk assessment procedures.
  - Accident and sickness records for the past five years.
  - Records of previous Health and Safety Executive enforcement action.
  - Records of training and training policy.
  - The number and type of staff responsible for health and safety on this project with details of their qualifications and duties.
- Submit: Within one week of request.

### 570 OUTLINE CONSTRUCTION PHASE HEALTH AND SAFETY PLAN

- Content: Submit the following information within one week of request:
  - Method statements on how risks from hazards identified in the pre-construction information and other hazards identified by the contractor will be addressed.
  - Details of the management structure and responsibilities.
  - Arrangements for issuing health and safety directions.
  - Procedures for informing other contractors and employees of health and safety hazards.
  - Selection procedures for ensuring competency of other contractors, the self-employed and designers.
  - Procedures for communications between the project team, other contractors and site operatives.
  - Arrangements for cooperation and coordination between contractors.
  - Procedures for carrying out risk assessment and for managing and controlling the risk.
  - Emergency procedures including those for fire prevention and escape.
  - Arrangements for ensuring that all accidents, illness and dangerous occurrences are recorded.
  - Arrangements for welfare facilities.
  - Procedures for ensuring that all persons on site have received relevant health and safety information and training.
  - Arrangements for consulting with and taking the views of people on site.
  - Arrangements for preparing site rules and drawing them to the attention of those affected and ensuring their compliance.
  - Monitoring procedures to ensure compliance with site rules, selection and management procedures, health and safety standards and statutory requirements.
  - Review procedures to obtain feedback.

### 599 FREEDOM OF INFORMATION ACT

- Records: Retain, make available for inspection and supply on request information reasonably required to allow response to requests made under the provisions of the Freedom of Information Act.
- Determination: Submit requests received. Do not supply information to anyone other than the project participants without express written permission.
- Confidentiality: Maintain at all times.

### **SUBLETTING/ SUPPLY**

## **A31 PROVISION, CONTENT AND USE OF DOCUMENTS**

### **DEFINITIONS AND INTERPRETATIONS**

#### **110 DEFINITIONS**

- Meaning: Terms, derived terms and synonyms used in the preliminaries/ general conditions and specification are as stated here or in the appropriate referenced document.

#### **120 COMMUNICATION**

- Definition: Includes advise, inform, submit, give notice, instruct, agree, confirm, seek or obtain information, consent or instructions, or make arrangements.
- Format: In writing to the person named in clause A10/140 unless specified otherwise.
- Response: Do not proceed until response has been received.

#### **130 PRODUCTS**

- Definition: Materials, both manufactured and naturally occurring, and goods, including components, equipment and accessories, intended for the permanent incorporation in the Works.
- Includes: Goods, plant, materials, site materials and things for incorporation into the Works.

#### **135 SITE EQUIPMENT**

- Definition: Apparatus, appliances, machinery, vehicles or things of whatsoever nature required in or about the construction for the execution and completion of the Works but not materials or other things intended to form or forming part of the Permanent Works.
- Includes: Construction appliances, vehicles, consumables, tools, temporary works, scaffolding, cabins and other site facilities.
- Excludes: Products and equipment or anything intended to form or forming part of the permanent works.

#### **140 DRAWINGS**

- Definitions: To BSRIA BG 6, 'A design framework for building services: Design activities and drawing definitions'.
- CAD data: In accordance with ISO 19650.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

## 160 TERMS USED IN SPECIFICATION

- Remove: Disconnect, dismantle as necessary and take out the designated products or work and associated accessories, fixings, supports, linings and bedding materials. Dispose of unwanted materials. Excludes removal and disposal of associated pipework, wiring, ductwork or other services.
- Remediate: Action or measures taken to lessen, clean up, remove or mitigate the existence of hazardous materials; in accordance with standards, or requirements as may be set out by statutes, rules, regulations or specification.
- Fix: Receive, unload, handle, store, protect, place and fasten in position; dispose of waste and surplus packaging. To include all labour, materials and site equipment for that purpose.
- Supply and fix: As above, but including supply of products, components or systems to be fixed, together with everything necessary for their fixing. All products, components or systems are to be supplied and fixed unless stated otherwise.
- Keep for reuse: Do not damage designated products or work. Clean off bedding and jointing materials. Stack neatly, protect adequately and store until required by the employer/ purchaser, or until required for use in the works as instructed.
- Keep for recycling: As 'keep for reuse', but relates to a naturally occurring material rather than a manufactured product.
- Make good: Execute local remedial work to designated work. Make secure, sound and neat. Excludes redecoration and/ or replacement.
- Replace: Supply and fix new products matching those removed. Execute work to match original new state of that removed.
- Repair: Execute remedial work to restore something to its original working state. Make secure, sound and neat. Excludes redecoration and/ or replacement.
- Refix: Fix removed products.
- Ease: Adjust moving parts of designated products, or work to achieve free movement and good fit in open and closed positions.
- Match existing: Provide products and work of the same appearance and features as the original, excluding ageing and weathering. Make joints between existing and new work as inconspicuous as possible.
- System: Equipment, accessories, controls, supports and ancillary items (including installation) necessary for that section of the work to function.

## 170 MANUFACTURER AND PRODUCT REFERENCE

- Definition: When used in this combination:
  - Manufacturer: the person or legal entity under whose name or trademark the particular product, component or system is marketed
  - Product reference: the proprietary brand name and/ or identifier by which the particular product, component or system is described.
- Currency: References are to the particular product as specified in the manufacturer's technical literature current on the date of the invitation to tender.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 200 SUBSTITUTION OF PRODUCTS

- Products: If an alternative product to that specified is proposed, obtain approval before ordering the product.
- Reasons: Submit reasons for the proposed substitution.
- Documentation: Submit relevant information, including:
  - manufacturer and product reference;
  - cost;
  - availability;
  - relevant standards;
  - performance;
  - function;
  - compatibility of accessories;
  - proposed revisions to drawings and specification;
  - compatibility with adjacent work;
  - appearance;
  - copy of warranty/ guarantee.
- Alterations to adjacent work: If needed, advise scope, nature and cost.
- Manufacturers' guarantees: If substitution is accepted, submit before ordering products.

### 210 CROSS REFERENCES

- Accuracy: Check remainder of the annotation or item description against the terminology used in the section or clause referred to.
- Related terminology: Where a numerical cross-reference is not given the relevant sections and clauses of the specification will apply.
- Relevant clauses: Clauses in the referred to specification section dealing with general matters, ancillary products and execution also apply.
- Discrepancy or ambiguity: Before proceeding, obtain clarification or instructions.

### 220 REFERENCED DOCUMENTS

- Conflicts: Specification prevails over referenced documents.

### 230 EQUIVALENT PRODUCTS

- Inadvertent omission: Wherever products are specified by proprietary name the phrase 'or equivalent' is to be deemed included.

### 240 SUBSTITUTION OF STANDARDS

- Specification to British Standard or European Standard: Substitution may be proposed complying with a grade or category within a national standard of another Member State of the European Community or an international standard recognised in the UK.
- Before ordering: Submit notification of all such substitutions.
- Documentary evidence: Submit for verification when requested as detailed in clause A31/200. Any submitted foreign language documents must be accompanied by certified translations into English.

### 250 CURRENCY OF DOCUMENTS AND INFORMATION

- Currency: References to published documents are to the editions, including amendments and revisions, current on the date of the Invitation to Tender.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

260 SIZES

- General dimensions: Products are specified by their co-ordinating sizes.
- Timber: Cross section dimensions shown on drawings are:
  - Target sizes as defined in BS EN 336 for structural softwood and hardwood sections.
  - Finished sizes for non-structural softwood or hardwood sawn and further processed sections.

**DOCUMENTS PROVIDED ON BEHALF OF THE EMPLOYER**

410 ADDITIONAL COPIES OF DRAWINGS/ DOCUMENTS

- Additional copies: Issued free of charge.

440 DIMENSIONS

- Scaled dimensions: Do not rely on.

450 MEASURED QUANTITIES

- Ordering products and constructing the Works: The accuracy and sufficiency of the measured quantities is not guaranteed.
- Precedence: The specification and drawings shall override the measured quantities.

460 THE SPECIFICATION

- Coordination: All sections must be read in conjunction with Main Contract Preliminaries/ General conditions.

**DOCUMENTS PROVIDED BY CONTRACTOR/ SUBCONTRACTORS/ SUPPLIERS**

630 TECHNICAL LITERATURE

- Information: Keep on site for reference by all supervisory personnel:
  - Manufacturers' current literature relating to all products to be used in the Works.
  - Relevant British, EN or ISO Standards.

640 MAINTENANCE INSTRUCTIONS AND GUARANTEES

- Components and equipment: Obtain or retain copies, register with manufacturer and hand over on or before completion of the Works.
- Information location: In Building Manual.
- Emergency call out services: Provide telephone numbers for use after completion. Extent of cover: twenty four hours seven days a week .



## **A32 MANAGEMENT OF THE WORKS**

### **GENERALLY**

#### **110 SUPERVISION**

- General: Accept responsibility for coordination, supervision and administration of the Works, including subcontracts.
- Coordination: Arrange and monitor a programme with each subcontractor, supplier, local authority and statutory undertaker, and obtain and supply information as necessary for coordination of the work.

#### **120 INSURANCE**

- Documentary evidence: Before starting work on site submit details, and/ or policies and receipts for the insurances required by the Conditions of Contract.

#### **130 INSURANCE CLAIMS**

- Notice: If any event occurs which may give rise to any claim or proceeding in respect of loss or damage to the Works or injury or damage to persons or property arising out of the Works, immediately give notice to the employer/ client, the person administering the Contract on their behalf and the Insurers.
- Failure to notify: Indemnify the employer/ client against any loss, which may be caused by failure to give such notice.

#### **140 CLIMATIC CONDITIONS**

- Information: Record accurately and retain:
  - Daily maximum and minimum air temperatures (including overnight).
  - Delays due to adverse weather, including description of the weather, types of work affected and number of hours lost.

#### **150 OWNERSHIP**

- Alteration/ clearance work: Materials arising become the property of the Contractor except where otherwise stated. Remove from site as work proceeds.

### **PROGRAMME/ PROGRESS**

#### **210 PROGRAMME**

- Master programme: Immediately when requested and before starting work on site submit in an approved form a master programme for the Works, which must include details of:
  - Planning and mobilisation by the Contractor
  - Subcontractor's work.
  - Running in, adjustment, commissioning and testing of all engineering services and installations.
  - Work resulting from instructions issued in regard to the expenditure of provisional sums.
  - Work by others concurrent with the Contract.
- Submit two copies.

#### **245 START OF WORK ON SITE**

- Notice: Before the proposed date for start of work on site give minimum notice of one week.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 250 MONITORING

- Progress: Record on a copy of the programme kept on site.
- Avoiding delays: If any circumstances arise which may affect the progress of the Works submit proposals or take other action as appropriate to minimize any delay and to recover any lost time.
- Key Performance Indicators:
  - Details: Time, cost and quality.
  - Performance: Record progress against each KPI.
  - Corrective action: If performance falls below target, submit proposals as soon as possible.

### 260 SITE MEETINGS

- General: Site meetings will be held to review progress and other matters arising from administration of the Contract.
- Frequency: Every two weeks.
- Location: At site.
- Accommodation: Ensure availability at the time of such meetings.
- Attendees: Attend meetings and inform subcontractors and suppliers when their presence is required.
- Chairperson (who will also take and distribute minutes): Contract Administrator .

### 290 NOTICE OF COMPLETION

- Requirement: Give notice of the anticipated dates of completion of the whole or parts of the Works.
- Associated works: Ensure necessary access, services and facilities are complete.
- Period of notice (minimum): Two weeks.

### 310 EXTENSIONS OF TIME

- Notice: When a notice of the cause of any delay or likely delay in the progress of the works is given under the contract, written notice must also be given of all other causes which apply concurrently.
- Details: As soon as possible submit:
  - Relevant particulars of the expected effects, if appropriate, related to the concurrent causes.
  - An estimate of the extent, if any, of the expected delay in the completion of the Works beyond the date for completion.
  - All other relevant information required.

## **CONTROL OF COST**

### 420 REMOVAL/ REPLACEMENT OF EXISTING WORK

- Extent and location: Agree before commencement.
- Execution: Carry out in ways that minimize the extent of work.

### 430 PROPOSED INSTRUCTIONS

- Estimates: If a proposed instruction requests an estimate of cost, submit without delay and in any case within seven days.

### 440 MEASUREMENT

- Covered work: Give notice before covering work required to be measured.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

450 DAYWORK VOUCHERS

- Before commencing work: Give reasonable notice to person countersigning daywork vouchers.
- Content: Before delivery each voucher must be:
  - Referenced to the instruction under which the work is authorised.
  - Signed by the Contractor's person in charge as evidence that the operatives' names, the time daily spent by each and the equipment and products employed are correct.
- Submit: By the end of the week in which the work has been executed.

470 PRODUCTS NOT INCORPORATED INTO THE WORKS

- Ownership: At the time of each valuation, supply details of those products not incorporated into the Works which are subject to any reservation of title inconsistent with passing of property as required by the Conditions of Contract, together with their respective values.
- Evidence: When requested, provide evidence of freedom of reservation of title.

## **A33 QUALITY STANDARDS/ CONTROL**

### **STANDARDS OF PRODUCTS AND EXECUTIONS**

#### **110 INCOMPLETE DOCUMENTATION**

- General: Where and to the extent that products or work are not fully documented, they are to be:
  - Of a kind and standard appropriate to the nature and character of that part of the Works where they will be used.
  - Suitable for the purposes stated or reasonably to be inferred from the project documents. Contract documents: Omissions or errors in description and/ or quantity shall not vitiate the Contract nor release the Contractor from any obligations or liabilities under the Contract.

#### **120 WORKMANSHIP SKILLS**

- Operatives: Appropriately skilled and experienced for the type and quality of work.
- Registration: With Construction Skills Certification Scheme.
- Evidence: Operatives must produce evidence of skills/ qualifications when requested.

#### **130 QUALITY OF PRODUCTS**

- Generally: New. (Proposals for recycled products may be considered).
- Supply of each product: From the same source or manufacturer.
- Whole quantity of each product required to complete the Works: Consistent kind, size, quality and overall appearance.
- Tolerances: Where critical, measure a sufficient quantity to determine compliance.
- Deterioration: Prevent. Order in suitable quantities to a programme and use in appropriate sequence.

#### **135 QUALITY OF EXECUTION**

- Generally: Fix, apply, install or lay products securely, accurately, plumb, neatly and in alignment.
- Colour batching: Do not use different colour batches where they can be seen together.
- Dimensions: Check on-site dimensions.
- Finished work: Without defects, e.g. not damaged, disfigured, dirty, faulty, or out of tolerance.
- Location and fixing of products: Adjust joints open to view so they are even and regular.

#### **140 EVIDENCE OF COMPLIANCE**

- Proprietary products: Retain on site evidence that the proprietary product specified has been supplied.
- Performance specification: Submit evidence of compliance, including test reports indicating:
  - Properties tested.
  - Pass/ fail criteria.
  - Test methods and procedures.
  - Test results.
  - Identity of testing agency.
  - Test dates and times.
  - Identities of witnesses.
  - Analysis of results.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 150 INSPECTIONS

- Products and executions: Inspection or any other action must not be taken as approval unless confirmed in writing referring to:
  - Date of inspection.
  - Part of the work inspected.
  - Respects or characteristics which are approved.
  - Extent and purpose of the approval.
  - Any associated conditions.

### 160 RELATED WORK

- Details: Provide all trades with necessary details of related types of work. Before starting each new type or section of work ensure previous related work is:
  - Appropriately complete.
  - In accordance with the project documents.
  - To a suitable standard.
  - In a suitable condition to receive the new work.
- Preparatory work: Ensure all necessary preparatory work has been carried out.

### 170 MANUFACTURER'S RECOMMENDATIONS/ INSTRUCTIONS

- General: Comply with manufacturer's printed recommendations and instructions current on the date of the Invitation to tender.
- Exceptions: Submit details of changes to recommendations or instructions.
- Execution: Use ancillary products and accessories supplied or recommended by main product manufacturer.
- Products: Comply with limitations, recommendations and requirements of relevant valid certificates.

### 180 WATER FOR THE WORKS

- Mains supply: Clean and uncontaminated.
- Other: Do not use until:
  - Evidence of suitability is provided.
  - Tested to BS EN 1008 if instructed.

## **SAMPLES/ APPROVALS**

### 210 SAMPLES

- Products or executions: Comply with all other specification requirements and in respect of the stated or implied characteristics either:
  - To an express approval.
  - To match a sample expressly approved as a standard for the purpose.

### 220 APPROVAL OF PRODUCTS

- Submissions, samples, inspections and tests: Undertake or arrange to suit the Works programme.
- Approval: Relates to a sample of the product and not to the product as used in the Works. Do not confirm orders or use the product until approval of the sample has been obtained.
- Complying sample: Retain in good, clean condition on site. Remove when no longer required.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 230 APPROVAL OF EXECUTION

- Submissions, samples, inspections and tests: Undertake or arrange to suit the Works programme.
- Approval: Relates to the stated characteristics of the sample. (If approval of the finished work as a whole is required this is specified separately). Do not conceal, or proceed with affected work until compliance with requirements is confirmed.
- Complying sample: Retain in good, clean condition on site. Remove when no longer required.

### **ACCURACY/ SETTING OUT GENERALLY**

### 320 SETTING OUT

- General: Submit details of methods and equipment to be used in setting out the Works.
- Levels and dimensions: Check and record the results on a copy of drawings. Notify discrepancies and obtain instructions before proceeding.
- Inform: When complete and before commencing construction.

### 330 APPEARANCE AND FIT

- Tolerances and dimensions: If likely to be critical to execution or difficult to achieve, as early as possible either:
  - Submit proposals; or
  - Arrange for inspection of appearance of relevant aspects of partially finished work.
- General tolerances (maximum): To BS 5606, tables 1 and 2.

### **SERVICES GENERALLY**

### 410 SERVICES REGULATIONS

- New or existing services: Comply with the Byelaws or Regulations of the relevant Statutory Authority.

### 420 WATER REGULATIONS/ BYELAWS NOTIFICATION

- Requirements: Notify Water Undertaker of any work carried out to (or which affects) new or existing services and submit any required plans, diagrams and details.
- Consent: Allow adequate time to receive Undertaker's consent before starting work. Inform immediately if consent is withheld or is granted subject to significant conditions.

### 430 WATER REGULATIONS/ BYELAWS CONTRACTOR'S CERTIFICATE

- On completion of the work: Submit (copy where also required to the Water Undertaker) a certificate including:
  - The address of the premises.
  - A brief description of the new installation and/ or work carried out to an existing installation.
  - The Contractor's name and address.
  - A statement that the installation complies with the relevant Water Regulations or Byelaws.
  - The name and signature of the individual responsible for checking compliance.
  - The date on which the installation was checked.

### 435 ELECTRICAL INSTALLATION CERTIFICATE

- Submit: When relevant electrical work is completed.
- Original certificate: To be lodged in the Building Manual.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

445 SERVICE RUNS

- General: Provide adequate space and support for services, including unobstructed routes and fixings.
- Ducts, chases and holes: Form during construction rather than cut.
- Coordination with other works: Submit details of locations, types/ methods of fixing of services to fabric and identification of runs and fittings.

450 MECHANICAL AND ELECTRICAL SERVICES

- Final tests and commissioning: Carry out so that services are in full working order at completion of the Works.
- Building Regulations notice: Copy to be lodged in the Building Manual.

**SUPERVISION/ INSPECTION/ DEFECTIVE WORK**

525 ACCESS

- Extent: Provide at all reasonable times access to the Works and to other places of the Contractor or subcontractors where work is being prepared for the Contract.
- Designate: Contract Administrator .

530 OVERTIME WORKING

- Notice: Prior to overtime being worked, submit details of times, types and locations of work to be done.
  - Minimum period of notice: One week.
- Concealed work: If executed during overtime for which notice has not been given, it may be required to be opened up for inspection and reinstated at the Contractor's expense.

540 DEFECTS IN EXISTING WORK

- Undocumented defects: When discovered, immediately give notice. Do not proceed with affected related work until response has been received.
- Documented remedial work: Do not execute work which may:
  - Hinder access to defective products or work; or
  - Be rendered abortive by remedial work.

560 TESTS AND INSPECTIONS

- Timing: Agree and record dates and times of tests and inspections to enable all affected parties to be represented.
- Confirmation: One working day prior to each such test or inspection. If sample or test is not ready, agree a new date and time.
- Records: Submit a copy of test certificates and retain copies on site.

610 DEFECTIVE PRODUCTS/ EXECUTIONS

- Proposals: Immediately any work or product is known, or appears, to be not in accordance with the Contract, submit proposals for opening up, inspection, testing, making good, adjustment of the Contract Sum, or removal and re-execution.
- Acceptability: Such proposals may be unacceptable and contrary instructions may be issued.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

**WORK AT OR AFTER COMPLETION**

**710 WORK BEFORE COMPLETION**

- General: Make good all damage consequent upon the Works.
- Temporary markings, coverings and protective wrappings: Remove unless otherwise instructed.
- Cleaning: Clean the Works thoroughly inside and out, including all accessible ducts and voids. Remove all splashes, deposits, efflorescence, rubbish and surplus materials.
- Cleaning materials and methods: As recommended by manufacturers of products being cleaned, and must not damage or disfigure other materials or construction.
- COSHH dated data sheets: Obtain for all materials used for cleaning and ensure they are used only as recommended by their manufacturers.
- Minor faults: Touch up in newly painted work, carefully matching colour and brushing out edges. Repaint badly marked areas back to suitable breaks or junctions.
- Moving parts of new work: Adjust, ease and lubricate as necessary to ensure easy and efficient operation, including doors, windows, drawers, ironmongery, appliances, valves and controls.

**720 SECURITY AT COMPLETION**

- General: Leave the Works secure with, where appropriate, all accesses closed and locked.
- Keys: Account for and adequately label all keys, and hand over together with an itemized schedule, retaining duplicate schedule signed as a receipt.

**730 MAKING GOOD DEFECTS**

- Remedial work: Arrange access with Client.
- Rectification: Give reasonable notice for access to the various parts of the Works.
- Completion: Notify when remedial works have been completed.



## **A34 SECURITY/ SAFETY/ PROTECTION**

### **SECURITY, HEALTH AND SAFETY**

#### **120 EXECUTION HAZARDS**

- Common hazards: Not listed. Control by good management and site practice.
- Significant hazards: The design of the project includes the following:
  - Hazard: Refer to Pre-Construction Information.
  - Precautions assumed: Refer to Pre-Construction Information.
  - Specification reference: N/A.
  - Drawing reference: N/A.

#### **130 PRODUCT HAZARDS**

- Hazardous substances: Site personnel levels must not exceed occupational exposure standards and maximum exposure limits stated in the current version of HSE document EH40: Workplace Exposure Limits.
- Common hazards: Not listed. Control by good management and site practice.
- Significant hazards: Specified construction materials include the following:
  - Hazard: Refer to Pre-Construction Information.
  - Material: Refer to Pre-Construction Information.
  - Specification reference: N/A.

#### **140 CONSTRUCTION PHASE HEALTH AND SAFETY PLAN**

- Submission: Present to the Employer/ Client no later than two weeks before commencement of works.
- Confirmation: Do not start construction work until the Employer has confirmed in writing that the Construction Phase Health and Safety Plan includes the procedures and arrangements required by the CDM Regulations.
- Content: Develop the plan from and draw on the Outline Construction Phase Health and Safety Plan, clause A30/570, and the Pre-tender Health and Safety Plan/ Preconstruction information.

#### **150 SECURITY**

- Protection: Safeguard the site, the Works, products, materials, and any existing buildings affected by the Works from damage and theft.
- Access: Take all reasonable precautions to prevent unauthorized access to the site, the Works and adjoining property.
- Special requirements: Protect sites with HERAS fencing to prevent public access .

#### **160 STABILITY**

- Responsibility: Maintain the stability and structural integrity of the Works and adjacent structures during the Contract.
- Design loads: Obtain details, support as necessary and prevent overloading.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

**170 OCCUPIED PREMISES**

- Extent: Existing buildings will be occupied and/ or used during the Contract as follows: Main Beach Car Park: Public access to the area not outlined for resurfacing may need to be retained and for access and to house to the annual winter market.  
North Beach Car Park: 24/7 access for HM Coastguards employees and public and staff access to Swanage Town Football Club should be retained.  
De Moulham Estate: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period.  
Service Road off Northbrook Road: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period..
- Works: Carry out without undue inconvenience and nuisance and without danger to occupants and users.
- Overtime: If compliance with this clause requires certain operations to be carried out during overtime, and such overtime is not required for any other reason, the extra cost will be allowed, provided that such overtime is authorized in advance.

**210 SAFETY PROVISIONS FOR SITE VISITS**

- Safety: Submit details in advance of safety provisions and procedures (including those relating to materials, which may be deleterious), which will require their compliance when visiting the site.
- Protective clothing and/ or equipment: Provide and maintain on site for visitors to the site.

**PROTECT AGAINST THE FOLLOWING****340 POLLUTION**

- Prevention: Protect the site, the Works and the general environment including the atmosphere, land, streams and waterways against pollution.
- Contamination: If pollution occurs inform immediately, including to the appropriate Authorities and provide relevant information.

**350 PESTICIDES**

- Use: Not permitted.

**360 NUISANCE**

- Duty: Prevent nuisance from smoke, dust, rubbish, vermin and other causes.
- Surface water: Prevent hazardous build-up on site, in excavations and to surrounding areas and roads.

**370 ASBESTOS CONTAINING MATERIALS**

- Duty: Report immediately any suspected materials discovered during execution of the Works.
  - Do not disturb.
  - Agree methods for safe removal or encapsulation.

**371 DANGEROUS OR HAZARDOUS SUBSTANCES**

- Duty: Report immediately suspected materials discovered during execution of the Works.
  - Do not disturb.
  - Agree methods for safe removal or remediation.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### 375 ANTIQUITIES

- Duty: Report immediately any fossils, antiquities and other objects of interest or value discovered during execution of the Works.
- Preservation: Keep objects in the exact position and condition in which they were found.
- Special requirements: None.

### 380 FIRE PREVENTION

- Duty: Prevent personal injury or death, and damage to the Works or other property from fire.
- Standard: Comply with Joint Code of Practice 'Fire Prevention on Construction Sites', published by Construction Industry Publications and The Fire Protection Association (The 'Joint Fire Code').

### 390 SMOKING ON SITE

- Smoking on site: Not permitted.

### 400 BURNING ON SITE

- Burning on site: Not permitted.

### 410 MOISTURE

- Wetness or dampness: Prevent, where this may cause damage to the Works.
- Drying out: Control humidity and the application of heat to prevent:
  - Blistering and failure of adhesion.
  - Damage due to trapped moisture.
  - Excessive movement.

### 430 WASTE

- Includes: Rubbish, debris, spoil, surplus material, containers and packaging.
- General: Minimize production. Prevent accumulations. Keep the site and Works clean and tidy.
- Handling: Collect and store in suitable containers. Remove frequently and dispose of off-site in a safe and competent manner:
  - Non-hazardous material: In a manner approved by the Waste Regulation Authority.
  - Hazardous material: As directed by the Waste Regulation Authority and in accordance with relevant regulations.
- Recyclable material: Sort and dispose at a Materials Recycling Facility approved by the Waste Regulation Authority.
- Voids and cavities in the construction: Remove rubbish, dirt and residues before closing in.
- Waste transfer documentation: Retain on site.

### 470 INVASIVE SPECIES

- General: Prevent the spread of species (e.g. plants or animals) that may adversely affect the site or Works economically, environmentally or ecologically.
- Special precautions: None.
- Duty: Report immediately any suspected invasive species discovered during execution of the Works.
  - Do not disturb.
  - Agree methods for safe eradication or removal.

## Swanage Town Council - Resurfacing of Car Parks and Service Roads

### **PROTECT THE FOLLOWING**

#### **510 EXISTING SERVICES**

- Confirmation: Notify all service authorities, statutory undertakers and/ or adjacent owners of proposed works not less than one week before commencing site operations.
- Identification: Before starting work, check and mark positions of utilities/ services. Where positions are not shown on drawings obtain relevant details from service authorities, statutory undertakers or other owners.
- Work adjacent to services:
  - Comply with service authority's/ statutory undertaker's recommendations.
  - Adequately protect, and prevent damage to services: Do not interfere with their operation without consent of service authorities/ statutory undertakers or other owners.
- Identifying services:
  - Below ground: Use signboards, giving type and depth;
  - Overhead: Use headroom markers.
- Damage to services: If any results from execution of the Works:
  - Immediately give notice and notify appropriate service authority/ statutory undertaker.
  - Make arrangements for the work to be made good without delay to the satisfaction of service authority/ statutory undertaker or other owner as appropriate.
  - Any measures taken to deal with an emergency will not affect the extent of the Contractor's liability.
- Marker tapes or protective covers: Replace, if disturbed during site operations, to service authority's/ statutory undertakers recommendations.

#### **520 ROADS AND FOOTPATHS**

- Duty: Maintain roads and footpaths within and adjacent to the site and keep clear of mud and debris.
- Damage caused by site traffic or otherwise consequent upon the Works: Make good to the satisfaction of the Employer, Local Authority or other owner.

#### **530 EXISTING TOPSOIL/ SUBSOIL**

- Duty: Prevent over compaction of existing topsoil and subsoil in those areas which may be damaged by construction traffic, parking of vehicles, temporary site accommodation or storage of materials and which will require reinstatement prior to completion of the Works.
- Protection: Before starting work submit proposals for protective measures.

#### **540 RETAINED TREES/ SHRUBS/ GRASSED AREAS**

- Protection: Preserve and prevent damage, except those not required.
- Replacement: Mature trees and shrubs if uprooted, destroyed, or damaged beyond reasonable chance of survival in their original shape, as a consequence of the Contractor's negligence, must be replaced with those of a similar type and age at the Contractor's expense.

#### **550 RETAINED TREES**

- Protected area: Unless agreed otherwise do not:
  - Dump spoil or rubbish, excavate or disturb topsoil, park vehicles or plant, store materials or place temporary accommodation within an area which is the larger of the branch spread of the tree or an area with a radius of half the tree's height, measured from the trunk.
  - Sever roots exceeding 25 mm in diameter. If unintentionally severed give notice and seek advice.
  - Change level of ground within an area 3 m beyond branch spread.

# Swanage Town Council - Resurfacing of Car Parks and Service Roads

## 560 EXISTING FEATURES

- Protection: Prevent damage to existing buildings, fences, gates, walls, roads, paved areas and other site features, which are to remain in position during execution of the Works.
- Special requirements: None.

## 570 EXISTING WORK

- Protection: Prevent damage to existing work, structures or other property during the course of the work.
- Removal: Minimum amount necessary.
- Replacement work: To match existing.

## 580 BUILDING INTERIORS

- Protection: Prevent damage from exposure to the environment, including weather, flora, fauna, and other causes of material degradation during the course of the work.

## 620 ADJOINING PROPERTY

- Permission: Obtain as necessary from owners if requiring to erect scaffolding on or otherwise use adjoining property.

## 625 ADJOINING PROPERTY RESTRICTIONS

- Precautions:
  - Prevent trespass of workpeople and take precautions to prevent damage to adjoining property.
  - Pay all charges.
  - Remove and make good on completion or when directed.
- Damage: Bear cost of repairing damage arising from execution of the Works.

## 630 EXISTING STRUCTURES

- Duty: Check proposed methods of work for effects on adjacent structures inside and outside the site boundary.
- Supports: During execution of the Works:
  - Provide and maintain all incidental shoring, strutting, needling and other supports as may be necessary to preserve stability of existing structures on the site or adjoining that may be endangered or affected by the Works.
  - Do not remove until new work is strong enough to support existing structure.
  - Prevent overstressing of completed work when removing supports.
- Adjacent structures: Monitor and immediately report excessive movement.
- Standard: Comply with BS 5975 and BS EN 12812.

## 640 MATERIALS FOR RECYCLING/ REUSE

- Duty: Sort and prevent damage to stated products or materials, clean off bedding and jointing materials and other contaminants.
- Storage: Stack neatly and protect until required by the Employer or for use in the Works as instructed.

### **A35 SPECIFIC LIMITATIONS ON METHOD/ SEQUENCE/ TIMING**

130 METHOD/ SEQUENCE OF WORK

- Specific Limitations: Include the following in the programme:
  - Main Beach Car Park: Public access to the area not outlined for resurfacing may need to be retained and for access and to house to the annual winter market.
  - North Beach Car Park: 24/7 access for HM Coastguards employees and public and staff access to Swanage Town Football Club should be retained.
  - De Moulham Estate: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period.
  - Service Road off Northbrook Road: Access for occupiers of private properties from the lanes outlined for resurfacing may need to be maintained at some level for the contract period..

## **A36 FACILITIES/ TEMPORARY WORK/ SERVICES**

### **GENERALLY**

#### **110 SPOIL HEAPS, TEMPORARY WORKS AND SERVICES**

- Location: Give notice and details of intended siting.
- Maintenance: Alter, adapt and move as necessary. Remove when no longer required and make good.

### **ACCOMMODATION**

#### **230 TEMPORARY ACCOMMODATION**

- Proposals for temporary accommodation and storage for the Works: Submit two weeks prior to starting on site.
- Details to be included: Type of accommodation and storage, its siting and the programme for site installation and removal.

### **TEMPORARY WORKS**

#### **320 TEMPORARY WORKS**

- Employer's specific requirements: Provide: HERAS fencing for protection of the sites.

#### **340 NAME BOARDS/ ADVERTISEMENTS**

- General: Obtain approval, including statutory consents, and provide a temporary name board displaying:
  - Title of project: Resurfacing of Car Park.
  - Name of Employer: Swanage Town Council.
  - Names of Consultants: Dorset Council.
  - Names of Contractor and Subcontractors: To be confirmed.
  - Special requirements: A brief description of works being carried out.

### **SERVICES AND FACILITIES**

#### **420 LIGHTING AND POWER**

- Supply: Electricity from the existing mains may be used for the Works as follows:
  - Metering: Free of charge.
  - Point of supply: To be confirmed at pre-start meeting.
  - Available capacity: Contractor to check incoming supply.
  - Frequency: 50 Hz.
  - Phase: To be confirmed.
  - Current: Alternating.
- Continuity: No responsibility will be accepted for the consequences of failure or restriction in supply.

Swanage Town Council -  
Resurfacing of Car Parks and  
Service Roads

430 WATER

- Supply: The existing mains may be used for the Works as follows:
  - Metering: Free of charge.
  - Source: To be confirmed at pre-start meeting.
  - Location of supply point: To be confirmed.
  - Conditions/ Restrictions: Reasonable use.
- Continuity: No responsibility will be accepted for the consequences of failure or restriction in supply.

440 TELEPHONES

- Direct communication: As soon as practicable after the Date of Possession provide the Contractor's person in charge with a mobile telephone.



## **A37 OPERATION/ MAINTENANCE OF THE FINISHED WORKS**

### **GENERALLY**

#### **115 THE HEALTH AND SAFETY FILE**

- Responsibility: the contractor.
- Content: Obtain and provide the following information: This shall be a Health & Safety file incorporating the maintenance manual.
- Format: 1 hard copy and 1 PDF
- Delivery to: the Contract Administrator By (date): One week prior to practical completion.

#### **155 CONTENT OF THE BUILDING MANUAL**

- General: Details of the property, the parties, fire safety strategy, operational requirements and constraints of a general nature.
- Building fabric: Design criteria, maintenance details, product details, and environmental and trafficking conditions.
- Building services: Description and operation of systems, diagrammatic drawings, record drawings, identification of services, product details, equipment settings, maintenance schedules, consumable items, spares and emergency procedures.
- Documentation: Guarantees, warranties, maintenance agreements, test certificates and reports.

#### **160 PRESENTATION OF BUILDING MANUAL**

- Format: A4 size, plastics covered, loose leaf, four ring binders with hard covers, each indexed, divided and appropriately cover titled.
- Selected drawings needed to illustrate or locate items mentioned in the Manual: Where larger than A4, to be folded and accommodated in the binders so that they may be unfolded without being detached from the rings.
- As-built drawings: The main sets may form annexes to the Manual.

**A40 CONTRACTOR'S GENERAL COST ITEMS: MANAGEMENT AND  
STAFF**

- 110 MANAGEMENT AND STAFF
- Cost significant items: Site supervision.

**A41 CONTRACTOR'S GENERAL COST ITEMS: SITE  
ACCOMMODATION**

110 SITE ACCOMMODATION

- Details: Site accommodation required or made/ not made available by the Employer: See section A36.
- Cost significant items: Provision of storage and welfare if not made available by Employer .

**A43 CONTRACTOR'S GENERAL COST ITEMS: MECHANICAL PLANT**

- 110 MECHANICAL PLANT
- Cost significant items: Resurfacing plant.

**A44 CONTRACTOR'S GENERAL COST ITEMS: TEMPORARY WORKS**

110 TEMPORARY WORKS

- Details: Temporary works required or made/ not made available by the Employer: See section A36.
- Cost significant items: Protection of sites during the works.

## **A54 PROVISIONAL WORK/ ITEMS**

### **110 PROVISIONAL SUMS FOR DEFINED WORK**

- Item: All provisional sums are highlighted in schedule of works.
- Description of work: See schedule of works.
- Provisional Sums: Include See schedule of works.
- Allow for general attendance.

### **210 PROVISIONAL SUMS FOR UNDEFINED WORK**

- Item: All provisional sums are highlighted in the schedule of works.
- Description of work: See schedule of works.
- Provisional Sums: Include See schedule of works.
- Allow for general attendance.

### **590 CONTINGENCIES**

- Provisional sum: Include: £10,000 which is noted in the schedule of works.