



CAMELFORD TOWN COUNCIL

RESURFACING OF PATH IN ENFIELD PARK

SPECIFICATION

It is preferable if works could be undertaken at the same time as the riverbank repairs. Please see timings on Riverbank specification.

The section of path that needs resurfacing starts at the "Waterfall Bridge". It is the circular part of the path approximately 1km in length and 3m wide.

1. Preliminaries and project management.
2. Establishment of people and plant, protection barriers etc.
3. Supply, lay and compact a nominal 25mm thick layer of decorative surface/shingle aggregate on top of existing well compacted sub-base material forming 3m wide footpath.
4. Leave site clean and tidy.