

A	Prelims	Quantity	Unit	Rate	Total
A1	To bring and remove from site all plant required for the works.	1	Item		
A2	The setting out and taking levels for all works as specified and required throughout the implementation of the works.	1	Item		
A3	Design and resolution time on site which may arise.	1	Item		
A4	All necessary warning signs, barriers and temporary site fencing to be used during the contract (erection & removal).	1	Item		
A5	Welfare facilities as required by CDM Regs.	1	Item		
A6	Making good any existing site features not included within this contract which maybe damaged during the contract period.	1	Item		
B	Site clearance (SEE DRAWING NO. 188-01)	Quantity	Unit	Rate	Total
B1	Remove from site to recycling centre existing youth shelter	1	Item		
B2	Remove from site existing play equipment, allow for disposal at a local recycling centre (see site photo for range of existing equipment)	1	Item		
B3	Remove from site to a local recycling centre existing wetpour surface, advice should be sought from the local landfill operator (SITA) regarding the safe disposal of this material. Presume maximum depth of 130mm of wetpour surface.	235	m2		
B4	Remove from site and recycle existing lighting column, disconnection required and cable terminated at point A on drawing number 188-01	1	Item		
B5	Additional excavation to remove small grass area by service gate (20mm) and old path (towards old library) to depth of 160mm	1	m3		
B6	Remove existing bench and set aside for collection by client.				
C	Railings and gates	Quantity	Unit	Rate	Total
C1	Supply and install Pro safe gate.1m high 1.1m wide self closing gate from IAE Tel: 08451 777200. Include for removal of existing railing as required all excavations and concrete foundations for posts. Gates to be galvanised steel and powder coated in yellow RAL 1021.	1	Item		
D	Play equipment supply & install	Quantity	Unit	Rate	Total

D1	Supply and install 30m length Aerial Runway (no ramp required) available from Play & Leisure Ltd, Tel: 01244 546797 sales@playandleisure.org.uk	1	Item		
D2	Supply & install Cobra Swing ref (COB001) Available from Sutcliffe Play 01977 653 200 info@sutcliffeplay.co.uk	1	Item		
D3	Supply and install climbing frame Shoulderwalk & Slide (Ref: PZW424) Available from Sutcliffe Play 01977 653 200 info@sutcliffeplay.co.uk	1	Item		
D4	Supply and install a rota glide (ref RTGX) available from playdale on 015395 31561 info@playdale.co.uk	1	Item		
D5	Supply and install 4 Seat Cradle/Junior Swing available from Play & Leisure Ltd (SW08), Tel: 01244 546797 (Or very similar and approved).	1	Item		
D6	Supply and install cantilever basket swing available from Play & Leisure Limited, (Ref ECS5), Tel: 01244 546797 sales@playandleisure.org.uk	1	Item		
D7	Supply and install 1200 x 800mm spin dice play panel c/w steel posts available from http://www.corefabs.com	1	Item		
E	Playground surfacing including safety surfacing.	Quantity	Unit	Rate	Total
E1	Supply and install 50mm x 150mm x 900mm flat top pcc edgings.	203	Lin m		
E2	Excavate to 140mm depth all arisings to be taken to a local recycling centre. Arisings in the form of existing tarmac, grass, soil and stone base.	60	m3		
E2.1	Additional excavation for areas deeper than 40mm	3	m3		
E3	Supply and install geotextile	430	m2		
E4	MOT Type 1 100mm depth	43	m3		
E5	Tarmac wearing coat 20mm deep 6mm dense macadam (Close Graded) as per specification	106	m2		
E6	Tarmac base coat within play area and new link path 40mm deep (20mm aggregate) as per specification	106	m2		
F	Wetpour	Quantity	Unit	Rate	Total
F1	Supply and install purple wet pour for 'Aerial Runway' 40mm depth as per specification.	129	m2		

F2	Supply and install orange wetpour for 'Cobra Swing' 50mm depth as per specification.	34	m2		
F3	Supply and install blue wetpour for 'swings' 50mm depth as per specification.	42	m2		
F4	Supply and install Terracotta wetpour for 'Climbing Frame' 90mm depth vibrant colour as per specification.	23.5	m2		
F5	Supply and install Terracotta wetpour for 'Climbing Frame' 40mm depth vibrant colour as per specification.	21	m2		
F6	Supply and install bright yellow wetpour 40mm depth for 'Rota Glide' as per specification.	33	m2		
F7	Supply and install green/purple/blue mix wetpour to Basket swing as per specification 70mm deep	41	m2		
G	Reinstatement to tarmac by the aerial runway and old path				
G1	Excavate to 160mm depth	3.2	m3		
G2	Supply and install geotextile	20	m2		
G3	MOT Type 1 100mm depth	2	m3		
G4	Tarmac base coat within play area and new link path 40mm deep (20mm aggregate) as per specification	20	m2		
G5	Tarmac wearing coat 20mm deep 6mm dense macadam (Close Graded) as per specification	20	m2		
G6	Supply and install grade 1 quality topsoil to depth of 150mm	4	m2		
G7	Grass seed supply and application as per soft landscape specification.	4	m2		
			Sub-total		
			Contingency 7.5%		
			Grand Total		