



Potential supplier	A local blacksmith
Materials	Hand-forged steel. Steel galvanised, acid-etched and painted OR welded on site and finished with traditional paint system (not galvanised) - blacksmith to discuss options / pros and cons of each with client
Dimensions	tbc
Fixing	Root fixed into concrete footings
Lifespan	Approximately 30+ years
Cost per metre	££
Pros	<ul style="list-style-type: none"> Perhaps the option which would appear most likely to 'always have been there', best for an historic setting adjacent to a Scheduled Monument? A lightweight looking structure which would have minimal visual impact Possible with care to achieve nice detailing on changes of direction / angle etc Continuous handrail more pleasant to use Long lifespan is most relevant if a grander scheme is unlikely!
Cons	<ul style="list-style-type: none"> Mid-priced option? Tbc A relatively permanent solution which may hamper future surfacing improvements?

St. James's Park: Jubilee Steps Improvements

HANDRAIL OPTIONS: **Option 3— blacksmith– made: hand forged single rail and posts**

June 2023