Distribution Board Schedule



Create Consulting Engineers Ltd

HEAD OFFICE: - 15 Princes Street, Norwich, Norfolk, NR3 1AF, Tel: 01603 877010 Email: buildingservices@createconsultingengineers.co.uk

Client:	ECD Architects	Revision No.	Date	Prepared By	Additional Remarks		
Project:	Maritime and Coastguard Agency	P1.1	01/12/2017	NGS	Added Socket Outlet in Drying Room.		
Drawing No:	1321-CCE-00-XX-SH-E-70-P-1202				Added RCD protection to Drying Room Fan		
Designation:	ELP2						
Location:	Garage / Workshop						
Make:	EATON EBM182						
Revision No:	P1.1 Date : 17/11/2017						
Prepared By:	N.G.S. Checked By: J.D.B.						
File Reference:	N:\Projects\Maritime & Coastguard Agency\P17-1321 - Shrub End Clinic, Iceni Way, Colchester\Design\Building Services\Specification\[1321-CCE-00-XX-SH-E-70-P-1201_Distribution_Board_Chart.xlsx]EBM182 Phase 2						
General notes:	1) To be read in conjunction with the specification. 2) The Distribution Board will be supplied in 25mm ² 4 Core XLPE SWA and 25mm ² 6491B Main Bonding Conductor from the LV Distribution Board ELP1 Circuit 17T in the Phase 1Office Training Building.						

Circuit No.	Protective Device	Rating	Cable Type	Cable Size	CPC Size	Circuit Type	Number of Points	Circuit Description
1L1	Туре В	32A/30mA	6491B	4.0mm²	1.5mm²	Radial		Underfloor Heating Circuit No.1 - Garage/Workshop
1L2	Туре В	32A/30mA	6491B	4.0mm²	1.5mm²	Radial	1	Underfloor Heating Circuit No.2 - Garage/Workshop
1L3	Туре В	6A/30mA	6491B	2.5mm ²	1.5mm²	Radial	1	Underfloor Heating Circuit No.3 - Garage/Workshop
2L1	Туре В	6 Amp	6491B	1.5mm²	1.5mm²	Radial	1	Underfloor Heating Contactor Controls
2L2	Туре В	32A/30mA	6491B	2.5mm²	1.5mm²	Ring	10	Socket Outlets - Garage/ Workshop
2L3	Туре В	16A/30mA	6491B	2.5mm²	1.5mm²	Radial	1	Underfloor Heating Circuit - Drying Room
3L1	Туре В	6A/30mA	6491B	1.5mm²	1.5mm²	Radial	1	Extract Fan - Drying Room
3L2	Туре В	32A/30mA	6491B	2.5mm²	1.5mm²	Ring	10	Socket Outlets - Garage/ Workshop
3L3	Туре В	25A/30mA	6491B	4.0mm²	1.5mm²	Radial	1	Instantaneous Electric Water Heater - Workshop/Garage
4L1	Туре В	6 Amp	6491B	1.5mm²	1.5mm²	Lighting	10	Lighting - Workshop/Garage & External Flood Lights
4L2	Type B	32A/30mA	6491B	2.5mm²	1.5mm²	Ring	2	Sockets - External Wash-Down Area & Drying Room
4L3	Type B	6 Amp	6491B	1.5mm²	1.5mm ²	Radial	1	Extract Fan - Workshop/Garage
5T	Type C	20 Amp	6491B	2.5mm²	1.5mm²	Radial	1	Electrically Operated Roller Shutter Door #1
6T	Type C	20 Amp	6491B	2.5mm ²	1.5mm ²	Radial	1	Electrically Operated Roller Shutter Door #2
7L1	Type B	6 Amp	6491B	1.5mm²	1.5mm²	Lighting	4	Lighting - Drying Room & External Lighting
7L2								

Distribution Board Schedule



Create Consulting Engineers Ltd

HEAD OFFICE: - 15 Princes Street, Norwich, Norfolk, NR3 1AF, Tel: 01603 877010 Email: buildingservices@createconsultingengineers.co.uk

Client:	ECD Architects		Revision No.	Date	Prepa	red By	Additional Remarks	
Project:	Maritime and Coastguard Agenc	Су	P1.1	01/12/2017	NGS	~c	Added Socket Outlet in Drying Room.	
Drawing No:	1321-CCE-00-XX-SH-E-70-P-1202		P1.1			Added RCD protection to Drying Room Fan		
Designation:	ELP2							
Location:	Garage / Workshop							
Make:	EATON EBM182							
Revision No:	P1.1 Date : 17/11/2017							
Prepared By:	N.G.S. Checked By: J	.D.B.						
File Reference:	N:\Projects\Maritime & Coastguard Agency\P17-1321 - Shrub End Clinic, Iceni Way, Colchester\Design\Building Services\Specification\[1321-CCE-00-XX-SH-E-70-P-1201_Distribution_Board_Chart.xlsx]EBM182 Phase 2							
General notes:	1) To be read in conjunction with the specification. 2) The Distribution Board will be supplied in 25mm² 4 Core XLPE SWA and 25mm² 6491B Main Bonding Conductor from the LV Distribution Board ELP1 Circuit 17T in the Phase 10ffice Training Building.							
7L3								
8L1								
8L1 8L2								