

existing tarmacadam path

ramp up  
(tarmacadam)

ramp up  
(tarmacadam)

one brick wall  
under on 225mm  
thick concrete  
foundation

paving to be  
minimum one  
course below  
damp proof  
course and sloped  
away from  
building

450mm wide  
treads with  
brick-on-edge  
risers between  
225mm concrete  
foundation below

existing sink  
unit to be  
removed and  
all finishes  
made good

existing seats to  
remain

remove existing perspex  
roofing and supporting  
structure - make good all  
finishes disturbed.

insulate existing floor with  
100mm Celotex and  
22mm Flooring grade  
Chipboard and Altro  
Safety Flooring

Altro Atlas 40 type  
flooring suitable for  
spikes and studs (or  
similar approved)

Altro Atlas 40 type  
flooring suitable for  
spikes and studs (or  
similar approved)

new cupboard  
(Provisional Sum)

new suspended ceiling  
new vinyl floor  
walls re-decorated  
Skirting painted

new support  
(see Clause  
FOU5)

### Committee Room


2160

### Store

HyRoc cladding to  
shower areas

spaces shown for  
15 players

spaces shown for  
15 players



w.c.

w.c.

w.c.

w.c.

w.c.

w.c.

w.c.

w.c.

ex. 95 step

D16

D17

D18

remove existing fire wall above  
ceiling level. Replace with 50 x  
100mm s.w. @400mm c/c with  
bottom and top rails and  
intermediate noggins covered  
both sides with 13mm  
plasterboard. To give half hour  
fire resistance. Seal at junction  
with roof.



1500 dia  
clear space  
Disabled/  
Baby  
Changing

wash hand basins to be fito  
Cascade 360 x 300mm or  
similar approved. To be fitted  
with plunge type time  
operated mono bloc type tap

### Bar

2540

D9 Male  
w.c.

D10 Male  
w.c.

D6 F'male  
w.c.

D11 F'male  
w.c.

D8

D5

D12

D1

D2

D3

D4

D7

D8

D9

D10

D11

D12

D13

D14

D15

D16

D17

D18

D19

Decoration colours to be to Client's  
preference.  
Floors to W.C.s - Altro type non-slip

remove existing perspex  
roofing - prepare and  
supply and fix new  
troughed steel roofing.

existing walls  
lined with vapour  
barrier, softwood  
framing, 100mm  
Celotex, and  
13mm  
plasterboard and  
skim

paving ramped up  
to doorways to  
give level access.  
Adjust door  
opening to take  
account of raised  
floor level

450mm wide steps

ex. 70 x 130 channel

ex. 70 x 70 RHS

ex. 70 x 70 RHS

new p.c. paving (to match existing  
sizes and thickness) on sand  
blinded hardcore bed (laid in  
maximum 200mm layers).  
50mm dia. upvc weep holes at 2m  
c/c

ex. 70 x 130 channel

ex. 70 x 70 RHS

prepare, prime, and paint two  
coats black gloss paint to all  
steel framing

paving ramped up  
to doorways to  
give level access

new drain - ex. nwp to ditch

ex. 100mm  
dia. nwp

same arrangement  
as for D17

sewer

## Silverstone Recreational Association

Drawing No. - 2

Proposed Plan

Scale - 1:75

K.WILCOX M.A.I.C.S., M.R.S.P.H.,  
27 Braden Road, Greens Norton,  
Northants, NN12 8BS