NEC4 Engineering and Construction

Short Contract

FCRM Operational Framework – South East Hub				
A contract between	The Environment Agency			
	Horizon House			
	Deanery Road			
	Bristol			
	BS1 5AH			
And	Land & Water Services Ltd			
For	ENVKSLES Dredging Southern			
	Contract Forms - Contract Data - The Contractor's Offer and Client's Acceptance - Price List - Scope - Site Information			

	The Client is	
Name	Environment Agency	
Address for communications	Scott's Float Depot, Military 7PH	y Road, Playden, Rye, East Sussex TN
Address for electronic communications		
The works are	Removal of fluvial deposits Sluice Weir Lock.	from the river Medway downstream o
The site is	River Medway downstream Tonbridge, Kent TN12 5EL	n of Sluice Lock Weir, East Peckham,
The starting date is	16th August 2021	
The completion date is	31st October 2021	
The delay damages are	Nil	Per day
The <i>period</i> for reply is	2	weeks
The defects date is	52	weeks after Completion
The defects correction period is	4	weeks
The assessment day is	the last working day	of each month
The retention is	nil	%
The United Kingdom Housing Grants, Co	nstruction and Regeneration	Act (1996) does apply

definition of the Adjudicator. The referring Party pays the administrative charge made by the Institution. The

person appointed is also Adjudicator for later disputes.

The Client's Contract Data

The interest rate on late payment is	0.5	9/	6 per complete week	of delay.
		. 34		
For any one event, the liability of the Contractor to the Client for loss of or damage to the Client's property is limited to	£100,000			
The Client provides this insurance	None			
	• • • • • • • • • • • • • • • • • • •			
	Insurance 1	Table		
Event		Cov	er	Cover provided until
Loss of or damage to the works			replacement cost	The Client's certificate of Completion has been issued
Loss of or damage to Equipment, Plant and Materials			replacement cost	The defects Certificate
The Contractor's liability for loss of or damage to property (except the works, Plant and Materials and Equipment) and for bodily injury to or death of a person (not an employee of the Contractor) arising from or in connection with the Contractor's Providing the Works			mum £5,000,000 in lect of every claim out limit to the ber of claims	has been issued
Liability for death of or bodily injury to employees of the Contractor arising out of and in the course of their employment in connection with this contract			amount required by applicable law	
Failure of the Contractor to use the skill and care normally used by professionals providing works similar to the works		resp with	mum £1,000,000 in lect of every claim out limit to the ber of claims	12 years following Completion of the whole of the works or earlier termination
The Adjudicator nominating body is	The Adjudicator nominating body is The Institution		vil Engineers	
The tribunal is	litigation in the	e cour	ts	

Z1.0	Sub-contracting Sub-contracting			
Z1.1	The <i>Contractor</i> submits the name of each proposed subcontractor to the <i>Client</i> for acceptance. A reason for not accepting the subcontractor is that their appointment will not allow the <i>Contractor</i> to Provide the Works. The <i>Contractor</i> does not appoint a proposed subcontractor until the <i>Client</i> has accepted them.			
Z1.2	Payment to subcontractors and suppliers will be no more than 30 days from receipt of invoice.			
Z2.0	Environment Agency as a regulatory authority			
Z2.1	The Environment Agency's position as a regulatory authority and as <i>Client</i> under the contract is separate and distinct. Actions taken in one capacity are deemed not to be taken in the other.			
Z2.2	Where statutory consents must be obtained from the Environment Agency in its capacity as a regulatory authority, the <i>Contractor</i> is responsible for obtaining these and paying fees (unless stated otherwise in the Scope). The <i>Client's</i> acceptance of a tender and the <i>Client's</i> instruction or variation of the works does not constitute statutory approval or consent.			
Z2.3	An action by the Environment Agency as regulatory authority is not in its capacity as <i>Client</i> and is not a compensation event.			
Z3.0	Confidentiality & Publicity			
Z3.1	The Contractor may publicise the works only with the Client's written agreement.			
Z4.0	Correctness of Site Information			
Z4.1	Site Information about the ground, subsoil, ducts, cables, pipes and structures is provided in good faith by the <i>Client</i> but is not warranted correct. The <i>Contractor</i> checks the correctness of any such Site Information they rely on for the purpose of Providing the Works.			
Z5.0	The Contracts (Rights of Third Parties) Act 1999			
Z5.1	For the purposes of the Contracts (Rights of Third Parties) Act 1999, nothing in this contract confers or purports to confer on a third party any benefit or any right to enforce a term of this contract.			
Z6.0	Design			
Z6.1	Where design is undertaken, it is the obligation of the <i>Contractor</i> to ensure the use of skill and care normally used by professionals providing similar design services.			
Z6.2	The Contractor designs the parts of the works which the Scope states they are to design.			
Z6.3	The <i>Contractor</i> submits the particulars of their design as the Scope requires to the <i>Client</i> for acceptance. A reason for not accepting the <i>Contractor's</i> design is that it does not comply with either the Scope or the applicable law.			
	The Contractor does not proceed with the relevant work until the Client has accepted this design.			
Z6.4	The Contractor may submit their design for acceptance in parts if the design of each part can be assessed fully.			
Z 7.0	Change to Compensation Events			
Z7.1	Delete the text of Clause 60.1(11) and replace by:			
	The works are affected by any one of the following events			
	 War, civil war, rebellion revolution, insurrection, military or usurped power Strikes, riots and civil commotion not confined to the employees of the <i>Contractor</i> and subcontractors 			
	Ionising radiation or radioactive contamination from nuclear fuel or nuclear waste resulting from the combustion of nuclear fuel			
	 Radioactive, toxic, explosive or other hazardous properties of an explosive nuclear device Natural disaster 			
	 Fire and explosion Impact by aircraft or other device or thing dropped from them 			

Z7.2	Additional Compensation Event COVID-19	
	Managing and mitigating the impact of Covid 19 and working in accordance with Public Health England guidance, as may vary from time to time, until 30 June 2021.	
Z8.0	Framework Agreement	
Z8.1	The <i>Contractor</i> shall ensure at all times during this contract it complies with all the obligations and conditions of the Framework Agreement made with the <i>Client</i> .	
Z9.0	Termination	
Z9.1	Delete the text of Clause 92.3 and replace with:	
	If the <i>Contractor</i> terminates for Reason 1 or 6, the amount due on termination also includes 5% of any excess of a forecast of the amount due at Completion had there been no termination over the amount due on termination assessed as for normal payments.	
Z10.0	Data Protection	
Z10.1	The requirements of the Data Protection Schedule shall be incorporated into this contract	
Z11.0	Liabilities and Insurance	
Z11.1	Civil data protection claims and regulatory fines for breaches of Data Protection Legislation are excluded from any limit of liability stated.	

The Contractor's Contract Data The Contractor is Land & Water Services Ltd Name Weston Yard, Albury, Guildford, surrey, GU5 9AF Address for communications Address for electronic communications The fee percentage is As framework % The people rates are As framework category of person unit rate The published list of Equipment is As framework The percentage for adjustment for Equipment is As framework

The Contractor's Offer and Client's Acceptance

The Contractor offers to Provide the determined in accordance with thes	e Works in accordance with these <i>conditions of contract</i> for an amount to be e <i>conditions of contract</i> .
The offered total of the Prices is	£316,761.47
	Enter the total of the Prices from the Price List.
Signed on behalf of the Contractor	
Name	
Position	
Signature	
Date	16 th April 2021
	•
The Client accepts the Contractor's	Offer to Provide the Works
Signed on behalf of the Client	
Name	
Position	
Signature	
Date	

Price List

For those items with a 'Sum' unit, the *Contractor* is to be paid an amount for the item which is not adjusted if the quantity of work in the item changes: the *Contractor* enters the amount in the Price Column only: the Unit, Quantity and rate columns being left blank.

For other items, the *Contractor* is to be paid an amount for the item which is adjusted if the quantity of work in the item changes: the *Contractor* enters the amount in the Rate and Price Columns only; updates in Quantity adjusting the Price according to the Rate, as constrained within the Scope.

ltem Number	Description	Unit	Quantity	Rate	Price
1	Take 4 samples of the fluvial deposits within the section to be dredged (TQ6703948005 to TQ6724748170) and one from the spoil heap beside Sluice Lock. Samples to be analysed and a report provided to the <i>Client</i>	Sum			
2	Pre-start photographic condition survey	Sum			
3	Mobilisation, including welfare provision.	Sum			
4	Produce a pre-dredge bathometric survey of the section of channel.	Sum			
5	Remove from site first 200 cubic metres of previous years' dredged material that is upon the bank adjacent to the Sluice Weir lock. Arisings to be taken from site under a waste plan approved by the <i>Client</i> .	Sum			
6	Remove further previous years dredged material from upon the bank adjacent to the Sluice Weir lock, under the direction of the <i>Client</i> . Arisings to be taken from site under a waste plan approved by the <i>Client</i> .	m ³			
7	Dredging accumulated deposits from the channel, first 1,500 cubic metres. Silts to be taken from site under a waste plan approved by the <i>Client</i> .	Sum			
8	Dredging further accumulated deposits from the channel under the direction of the Client. Arisings to be taken from site under a waste plan approved by the <i>Client</i> .	m ³			
9	Produce a post-dredge bathometric survey of the section of channel.	Sum			
10	Demobilisation and re-instatement	Sum			
11	Post-delivery photographic condition survey.	Sum			
12	Production of H&S file	Sum			
13	Other (Contractor to specify)	Sum			
	Vegetation clearance along access to lock	Sum			
	I.	The total	of the Prices	£	316,761.47

Civil Engineering Standard Method of Measurement 4th edition (CESMM4) as per the Framework Price Workbook

Scope

1. Description of the works

The outcome of the works is to remove accumulated fluvial deposits from within the open sections of the river Medway between TQ6703948005 and TQ6724748170. In delivering the works, the Contractor shall:

- Take 4 samples of the fluvial deposits on the channel bed, equally spaced within the section to be dredged (TQ6703948005 to TQ6724748170) and one from the spoil heap beside Sluice Weir lock. The Contractor will have these samples analysed and share the report with the Client. The report will inform the Contractor's waste plan. Samples to be taken within two weeks of the starting date..
- 2. Develop a Waste Management Plan for the approval of the Client before dredging works commence.
- 3. Develop a contingency plan of action should hazardous material be discovered or suspected whilst dredging works are underway. The *Client* must be informed immediately should hazardous material be found or suspected within the site. Produce a pre-works bathometric survey of the section of channel to be dredged (TQ6703948005 to TQ6724748170). The survey must be delivered before dredging works commence in September and will inform the *Client's* instructions to the *Contractor* of where to remove the agreed quantities of deposits from the bed of the channel.
- Conduct a pre-start photographic condition record of the visible Site. The Contractor shall share the report with the Client before works commence.
- 5. A Flood Risk Activity Permit will not be required.
- 6. Undertake on-site mobilisation, including provision of compound and welfare facilities.
- 7. Provide such traffic management as may be required to facilitate delivery of the project, including obtaining required consents from the managing authority.
- 8. Undertake such vegetation management as shall be required to facilitate the works.
- 9. Remove 200m³ of previous years dredging arisings from the pile upon the bank of the river Medway beside the Sluice Weir lock.
- 10. The *Contractor* shall not remove arisings in excess of 200m³ from the pile upon the bank of the river Medway beside the Sluice Weir lock without obtaining prior written confirmation from the *Client*.
- 11. Removal of additional material from the spoil pile (Description of the works item 9 above) will be at the Client's discretion subject to the re-measurable rates set out in the Price List (item 6). Only one incomplete load (the final load) will be acceptable to the Client.
- 12. Remove 1,500m³ fluvial deposits from the River Medway between the sluice and midway towards Branbridges Road, TQ6703948005 to TQ6724748170, under the *Client's* direction.
- 13. The *Contractor* shall not remove silt in excess of 1,500m³, without obtaining prior written confirmation from the *Client*.
- 14. Removal of silts beyond 1,500m³ as specified above may be instructed by the *Client* at the *Client*'s discretion and subject to the re-measurable rates set out in the Price List (item 8). Only one incomplete load (the final load) will be acceptable to the *Client*.
- 15. Fluvial deposits and arisings must be taken away from site under a waste plan approved by the *Client*. The *Contractor* is encouraged to investigate options for reuse of the deposits.
- Produce a post-works bathometric survey of the section of channel dredged (TQ6703948005 to TQ6724748170).
- 17. Conduct a post-delivery photographic condition record of the visible Site. The *Contractor* shall share the report with the *Client* within 14 days of demobilisation.
- 18. Remediate any damage caused (including to property) during the course of delivering the works
- 19. Produce a H&S file under the guidance of the Principal Designer.

In delivering the works, the Contractor shall:

 Develop a Construction Phase Plan (CPP) in accordance with the Environment Plan included within the Pre-Contract Information. The CPP must be offered for review by the *Client* and the Principal Designer prior to commencement of works on site.

- Liaise with the Client and the Principal Designer on matters relating to the delivery of the project, compliance with the CDM regulations, flood risk management, regulatory compliance, ecological stewardship and the programme.
- Register for flood alerts.
- Fulfil the duties of both Principal Contractor and Designer in terms of the CDM 2015 regulations. Duties
 will include, but are not limited to, producing the buildability statement, Designer's risk assessment,
 completing the RAG list and liaising with the Client and Principal Designer.
- Protect the Client's reputation by maintaining good relations with neighbouring residents and the public in general.
- Until the results of the 4 samples are confirmed, the Contractor may assume that the silt sample
 analysis reports that they will provide are similar in nature to those provided within the tender pack (that
 the deposits are no more hazardous than previous report have suggested). However, no dredging
 works must be undertaken until the new sampling analysis is available and the Waste Plan has been
 approved by the Client.

	- 10	-	/I I	~
2.		dV	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
			40. 基.现	
		CI VI		ıgs

Drawing Number	Revision	Title

3. Specifications

Title	Date or Revision	Tick if publicly available
Environment Agency Blockage Management Guide (Gov.uk)	12/2019	yes

4. Constraints on how the Contractor Provides the Works

All dredging activities must be finalised before the end of October.

The Contractor shall not undertake any work prior to their Waste Management Plan being accepted by the Client.

Previous sampling of the deposits suggests that the material is not hazardous. As these samples will be over one year old when this project starts, the *Contractor* must take further samples to inform the waste plan. There remains residual risk that hazardous material may be present, that either is not detectable or is not within the sample zones. The *Contractor* shall not continue works if hazardous material is found, without obtaining prior written authorisation from the *Client*.

The *Contractor* shall work within the constraints as provided in the Pre-Construction Information (SHOv2_FBG2020_PCI-Medway Desilting11_12_SD01 external rev 1 23-9-20.docx), which is to include but is not limited to managing the hazard that these *works* could pose to resident Depressed River Mussels:

- 1. Work on the Medway sections shall be programmed to take place in September and October of 2021.
- The Contractor shall not dredge a marginal exclusion zone of 1m.

3. The Contractor shall cease dredging if silts are being removed and seek advice from the Client.

Working times

The Contractor will be permitted to work between 7.30am and 6.00pm on weekdays (Monday to Friday)

5. Requirements for the programme

The *Contractor* submits his programme with the *Contractor*'s Offer for acceptance. The *Contractor* shows on each programme which he submits for acceptance (in form of Gantt chart showing the critical path, proposed order and timing to undertake the works and proposed plant and labour resources) the following:

- (a) Period required for mobilisation/ planning & post contract award
- (b) starting date
- (c) Each of the activities listed within the Price List
- (d) Any key third party interfaces: lead in periods for materials and sub-contractors; time required to obtain consents/waste permits; stated constraints; *Contractor's* risks.
- (e) Completion date

6. Services and other things provided by the Client

Item	Date by which it will be provided
Flood warnings and alerts	As soon as the Contractor registers
Service Plans	Within the tender pack
The Client will liaise with the landowner and neighbours.	Ongoing
Notices of Entry will be issued as demanded by the Designer's access plans.	Once the CPP has been produced to the satisfaction of the <i>Client</i> and Principal Designer.

Site Information

Please refer to the Pre-Contract Information/Environment Plans provided within the tender pack.

Service plans for each site provided within the tender pack.

Fish and eels may be present on each site.

The river Medway usually has higher flow volumes from the beginning of November until the end of winter as a consequence of higher seasonal rainfall.

Proposed sub-contractors				
	Name and address of proposed subcontractor	Nature and extent of work		
1.				
	Form of Contract:			
2.	Form of Contract:			
3.	Form of Contract:			
4.	Form of Contract:			