

THIS DRAWING IS INDICATIVE AND REPRESENTS ONLY THE DESIGN INTENT, THE CONTRACTOR MUST PRODUCE FULLY CO-ORDINATED WORKING / INSTALLATION DRAWINGS AS REFERRED TO IN THE CONTRACT DOCUMENTATION

- 1. DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS INDICATED ARE IN MILLIMETRES
- 2. DRAWING TO BE READ IN CONJUNCTION WITH SPECIFICATION, DOCUMENTATION, DRAWINGS & ALL RELEVANT BRITISH STANDARD **DOCUMENTS**
- 3. ALL ELECTRICAL WORKS SHALL COMPLY WITH 18TH EDITION IET WIRING REGS BS7671:2018 (2018). INCLUDING ALL CURRENT AMENDMENTS AND GUIDANCE NOTES AND THE CURRENT BUILDING STANDARDS REGULATIONS
- 4. THE INSTALLATION SHALL ONLY BE CERTIFIED BY A PERSON OR A COMPANY HAVING MEMBERSHIP TO S.E.L.E.C.T. OR N.I.C.E.I.C. OR SIMILAR ELECTRICAL SCHEMES
- 5. ALL CABLE TRAY & BASKET TO BE MEDIUM GRADE GALVANISED STAINLESS STEEL. ALL SIZES AS NOTED
- 6. ALL CABLE CONTAINMENT TO HAVE TRAFFOLYTE LABEL INSTALLED AT BOTH TERMINATION POINTS AND THROUGH ALL PENETRATIONS.
- 7. FINAL LOCATIONS OF ALL FIRE ALARM PANELS/DEVICES TO BE COORDINATED WITH ARCHITECT
- 8. SECONDARY CONDUITS TO BE PROVIDED BY THE CONTRACTOR

<u>LEGEND</u>

SUBMAIN CABLE TRAY

LIGHTING & POWER CABLE TRAY

COMMS CABLE BASKET

FIRE ALARMS CABLE TRAY

CABLE TRUNKING

CONTAINMENT SET UP

CONTAINMENT SET DOWN

PANELBOARD DISTRIBUTION BOARD

FAP FIRE ALARM PANEL

INTRUDER ALARM PANEL

AV/COMMS EQUIPMENT RACK

 SM
 AJ
 AJ
 27.10.21

 SM
 AJ
 AJ
 15.10.21

 SM
 AJ
 AJ
 01.10.21
BY CHK APP DATE REV DESCRIPTION Project Status:

TENDER

HARLEY

HADDOW

The Multi-disciplinary Engineering Consultancy Ground Floor, 45 Great Guildford Street London, SE1 0ES T 44 (0) 203 735 5060 E london@harleyhaddow.com Edinburgh I London I Glasgow

harleyhaddow.com

Project: 307685

HORNIMAN MUSEUM STAFF RECEPTION & REST AREA REFURBISHMENT

Drawing Title:

CONTAINMENT LAYOUT

307685-HAH-ZZ-01-DR-E-06110 P03