

Project
Wivelsfield Village Hall - New Extensions
 Client
Wivelsfield Village Hall

Project No
C-1732
 Reference #
(31)010 T1
 Revision
T1
 Reason for Issue
TENDER



Door Schedule -Ext/ Internal

08-Jun-20

Door #	PROPOSED Location	OPENING INTO Room #	Door Type NBS: L20 & drawing (31)010	Structural Opening		Door Leaf			Glazing / Vision panel	Fire resistance (S = Seal; SC = Self-closer)	Seals NBS: L20 S =Smoke	Frame Type See drawing C1732(31)011 for details	Lining depth & Materials (Also see notes below)	Colour	Ironmongery Group	SIGNAGE	FINGER PROTECTION	Comments
				Width (mm)	Height (mm)	Width(mm) Door leaf + Door leaf	Height (mm)	Thickness (mm)						Painted to match existing (TME)	NBS: P21			
DG01	Kitchen entrance (rear)	Refuse access	Ext3	1010	2100	926	2040	45 nom	none	none		FT1B	310 New timber rainscreen and blockwork	TME (Dark Grey)	1A	None	NONE	New door, frame, and ironmongery, to be set in new masonry cavity wall.
DG02	Kitchen side lobby (OMITTED)	Kitchen entrance lobby	Existing	n/a						none			n/a					Existing external door. Electronic locking to be transferred to DG01
DG03	Kitchen (OMITTED)	Kitchen Store	Int1	1010	2100	926	2040	35 nom	none	none		FT1B	300 New Masonry Cavity	TME	2	None	NONE	New door, frame, and ironmongery, to be set in new masonry cavity wall.
DG03A	Kitchen hatch	The Hall							none	FD30S	S							Size and shape to match existing
DG03B	Kitchen hatch shutter	The Hall	FIRE SHUTTER						none	FD30S	S							Size and shape to match existing
DG04	Hall Store	The Hall	Int7	1525	2100	752 + 752	2040	3	none	none		FT1B	290 New Masonry Cavity	TME	3	None	Hall side	New door, frame, and ironmongery, to be set in new masonry cavity wall.
DG05A	Hall Entrance Corridor	East Stairs	Int3A	910	2100	826	2040	35 nom	Safety Glass	FD30S SC	S	FT2A & FT2B	100 Exg.+New Blockwork	TME	4	Fire Door Keep Shut	Corridor side	New door, frame, and ironmongery, to be set in part Existing and New blockwork wall; on primary escape route; Self-closer and smoke seals.
DG05B	Hall Entrance Corridor	Under Stair cupboard	Int5	610	2100	526	2040	35 nom	none	FD30S	S	FT3	100 Plasterboard	TME	5	Fire Door Keep Shut	none	New door, frame, and ironmongery, to be set in new plasterboard stud partition; on primary escape route; smoke seals.
DG06	Hall Entrance Corridor	Toddlers WC	Int4A	910	2100	826	2040	35 nom	none	none	none	FT2B	100 New Blockwork	TME	6	Children WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer.
DG07	Hall Entrance Corridor	Reading Room	Int3B	910	2100	826	2040	35 nom	Safety Glass	FD30S SC	S	FT2B	100 New Blockwork	TME	7	Fire Door Keep Shut	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer and smoke seals
DG08	Hall Entrance Corridor	Female WC	Int4A	910	2100	826	2040	35 nom	none	none	none	FT2B	100 Exg. Blockwork	TME	6	Female WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer.
DG09	Hall Entrance Corridor	Disabled WC	Int2	1010	2100	926	2040	35 nom	none	none	none	FT1A & FT2A	100 New & 290 Exg. Blockwork	TME	8	Disabled WC	Both sides	New door, frame, and ironmongery, to be set in part new and existing block wall; on primary escape route.
DG10	Hall Entrance Corridor	Male WC	Int4A	910	2100	826	2040	35 nom	none	none	none	FT2B	100 New Blockwork	TME	6	Male WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer.
DG11	Store	Reading Room	Int6	910	2100	826	2040	35 nom	none	none	none	FT1A & FT1B	290 Exg.+New Masonry Cavity	TME	2	None	Reading Room side	New door, frame, and ironmongery, to be set in part new and existing block wall; on primary escape route; Self-closer.
DG12	Renshaw Room	New Store	Int6	1010	2100	926	2040	35 nom	none	none	none	FT1A & FT1B	290 Exg.+New Masonry Cavity	TME	2	None	Renshaw Room side	New door, frame, and ironmongery, to be set in part new and existing block wall; on primary escape route; Self-closer.
DG13	West Entrance Lobby	Council Office	Int3B	1010	2100	926	2040	35 nom	Safety Glass	FD30S SC	S	FT2B	100 New Blockwork	TME	9	Fire Door Keep Shut	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer and smoke seals
DG14	West Entrance Lobby	Male WC	Int4B	760	2100	676	2040	35 nom	none	none	none	FT2B	100 New Blockwork	TME	8	Male WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer.
DG15	West Entrance Lobby	Female WC	Int4B	760	2100	676	2040	35 nom	none	none	none	FT2B	100 New Blockwork	TME	8	Female WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route; Self-closer.
DG16	West Entrance Lobby	Disabled WC	Int2	1010	2100	752 + 752	2040	35 nom	none	none	none	FT2B	100 New Blockwork	TME	8	Disabled WC	Both sides	New door, frame, and ironmongery, to be set in new block wall; on primary escape route.
DG17	External Store	External fenced play area (south)	Ext2	1810	2100	858 + 858	2040	45 nom	none	none	none	FT4	310 New timber rainscreen and blockwork	TME (Dark Grey)	10	None	Both sides	New door, frame, and ironmongery, to be set in new acoustic stud partition; Self-closer.
WG08A	Hall Entrance	Entrance Foyer	WG08	3420	2075	880 + 880 (with 880 side lights each side)				SUPPLIED AS PART OF GLAZING / WINDOW PACKAGE				11	GLAZING MANIFESTATION	Integral to sliding door system	New sliding glazed door, frame, and ironmongery, to be set in new acoustic stud partition; Motorised Self-closer with PIR; See also C1732 (31)001 Window Schedule. Fit with manual override	
WG08B	Hall Entrance Foyer	Entrance Foyer	WG08	3420	2075	880 + 880 (with 880 side lights each side)				SUPPLIED AS PART OF GLAZING / WINDOW PACKAGE				11	GLAZING MANIFESTATION	Integral to sliding door system	New sliding glazed door, frame, and ironmongery, to be set in new acoustic stud partition; Motorised Self-closer with PIR; See also C1732 (31)001 Window Schedule. Fit with manual override	
WG13	Renshaw Fire Escape	Ext play area	WG13	910	2010	810 nom				SUPPLIED AS PART OF GLAZING / WINDOW PACKAGE				12	GLAZING MANIFESTATION	Both sides	New hinged glazed door, frame, and ironmongery as part of Glazing / Window; Manual Self-closer; See also C1732 (31)001 Window Schedule	
WG15A	Renshaw/Office Entrance	Lobby	WG15	2597.5	2085	1010				SUPPLIED AS PART OF GLAZING / WINDOW PACKAGE				13	GLAZING MANIFESTATION	Both sides	New hinged glazed door, frame, and ironmongery as part of Glazing / Window; Manual Self-closer; See also C1732 (31)001 Window Schedule	
WG15B	Renshaw/Office Lobby	Renshaw Room	WG15	2597.5	2085	1010				SUPPLIED AS PART OF GLAZING / WINDOW PACKAGE				13	GLAZING MANIFESTATION	Both sides	New hinged glazed door, frame, and ironmongery as part of Glazing / Window; Manual Self-closer; See also C1732 (31)001 Window Schedule	
DF01	Store/Meeting	West stair	Int3A	910	2100	826	2040	35 nom	Safety Glass	FD30S SC	S	FT3	100 Plasterboard	TME	6	Fire Door Keep Shut	Both sides	New door, frame, and ironmongery, to be set in new acoustic stud partition; Self-closer.
DF02	Under eaves storage 1	Store/Meeting	Int6	910	2100	826	2040	35 nom	none	none	none	FT3	100 Plasterboard	TME	6	None	Meeting Room side	New door, frame, and ironmongery, to be set in new acoustic stud partition; Self-closer.
DF03	Under eaves storage 2	Store/Meeting	Int6	910	2100	826	2040	35 nom	none	none	none	FT3	100 Plasterboard	TME	6	None	Meeting Room side	New door, frame, and ironmongery, to be set in new acoustic stud partition; Self-closer.

NOTES: ALL REVISIONS HIGHLIGHTED IN RED