

A10 PROJECT PARTICULARS

110 THE PROJECT

- Name: County Sessions House.
- Nature: Balustrade Repair.
- Location: William Brown Street, Liverpool L3 8BX.
- Length of contract: 8 weeks.

120 EMPLOYER (CLIENT)

- Name: National Museum Liverpool.
- Address: 127 Dale Street, Liverpool, L2 2JH.
- Contact: N/A .
- Telephone: N/A.
- E-mail: N/A.

130 PRINCIPAL CONTRACTOR (CDM)

- Name: TBA.
- Address: TBA.
- Contact: TBA.
- Telephone: TBA.
- E-mail: TBA.

140 ARCHITECT/ CONTRACT ADMINISTRATOR

- Name: National Museum Liverpool Estates Management Department.
- Address: 127 Dale Street, Liverpool, L2 2JH.
- Contact: N/A.
- Telephone: N/A.
- E-mail: N/A.

150 PRINCIPAL DESIGNER

- Name: National Museums Liverpool Estates Management Department.
- Address: 127 Dale Street, Liverpool, L2 2JH.
- Contact: N/A.
- Telephone: N/A.
- E-mail: N/A.

A11 TENDER AND CONTRACT DOCUMENTS

110 TENDER DRAWINGS

- The tender drawings are: Specification, Elevation Drawings, Health and Safety Documents.

120 CONTRACT DRAWINGS

- The Contract Drawings: The same as the tender drawings.

160 PRECONSTRUCTION INFORMATION

- Format: The Preconstruction information is described in these preliminaries in Section A34. It refers to information given elsewhere in the preliminaries and other tender documents.

180 OTHER DOCUMENTS

- Inspection: Drawings and other documents relating to the Contract but not included in the tender documents may be seen by appointment during normal office hours at the office of N/A.
- The documents include: N/A.

A12 THE SITE/ EXISTING BUILDINGS

110 THE SITE

- Description: The County Sessions House is used as offices, storage and public lectures. The area of work is restricted to the balustrades along William Brown Street and Mill Lane .

120 EXISTING BUILDINGS ON/ ADJACENT TO THE SITE

- Description: Walker Art Gallery.

180 HEALTH AND SAFETY FILE

- Availability for inspection: The Health and Safety File for the site/ building may be seen by appointment during normal office hours at: 127 Dale Street.
- Other documents: N/A.
- Arrangements for inspection: Mike Collins.

200 ACCESS TO THE SITE

- Description: Vehicle access is available via Mill Street and William Brown Street. .
- Limitations: Access to Mill Street and William Brown Street for unloading purposes only..

210 PARKING

- Restrictions on parking of the Contractor's and employees' vehicles: One vehicle parking space available on Walker Art gallery car park.

220 USE OF THE SITE

- General: Do not use the site for any purpose other than carrying out the Works.
- Limitations: 2.5 metres maximum work room between balustrade and site hoarding subject to Local Authority Agreement.

230 SURROUNDING LAND/ BUILDING USES

- General: Adjacent or nearby uses or activities are as follows:
 - Art Gallery and Offices.

240 HEALTH AND SAFETY HAZARDS

- General: The nature and condition of the site/ building cannot be fully and certainly ascertained before it is opened up. However the following hazards are or may be present:
 - Electric cabling attached to the rear balustrade along Mill Street elevation
 - Unidentified underground services..
- Information: The accuracy and sufficiency of this information is not guaranteed by the Employer or the Employer's representative. Ascertain if any additional information is required to ensure the safety of all persons and the Works.
- Site staff: Draw to the attention of all personnel working on the site the nature of any possible contamination and the need to take appropriate precautionary measures.

250 SITE VISIT

- Assessment: Ascertain the nature of the site, access thereto and all local conditions and restrictions likely to affect the execution of the Works.
- Arrangements for visit: via Mike Collins.

A20 JCT MINOR WORK BUILDING CONTRACT (MW)

JCT MINOR WORKS BUILDING CONTRACT

- The Contract: JCT Minor Works Building Contract 2011 Edition, incorporating amendment 1, March 2015..
- Requirement: Allow for the obligations, liabilities and services described.

THE RECITALS

First - THE WORKS AND THE CONTRACT ADMINISTRATOR

- The work comprises: Dismantling stone balustrade and renewing weathered components prior to reinstatement.
- Architect/ Contract Administrator: See clause A10/140.

Second - CONTRACT DOCUMENTS

- Contract drawings: As listed in clause A11/120.
Contract documents: The following have been prepared which show and describe the work to be done A specification.

Third - PRICED DOCUMENTS

- Documents to be priced or provided by the Contractor: Contract specification.

THE ARTICLES

3 - ARCHITECT/ CONTRACT ADMINISTRATOR

- Architect/ Contract Administrator: See clause A10/140.

4 and 5 - PRINCIPAL DESIGNER/ PRINCIPAL CONTRACTOR

- Articles 4 and 5 will be deleted

CONTRACT PARTICULARS

Fourth Recital and Schedule 2 - BASE DATE

- Base date: the date tenders are returned.

Fourth Recital and clause 4.2 - CONSTRUCTION INDUSTRY SCHEME (CIS)

- Employer at the Base Date is not a 'contractor' for the purposes of the CIS.

Fifth Recital - CDM REGULATIONS

- The project is not notifiable.

Seventh Recital and Schedule 3 - SUPPLEMENTAL PROVISIONS

- Collaborative working: Paragraph 1 applies.
- Health and safety: Paragraph 2 applies.
- Cost savings and value improvements: Paragraph 3 applies.
- Sustainable development and environmental considerations: Paragraph 4 applies.
- Performance indicators and monitoring: Paragraph 5 does not apply.
- Notification and negotiation of disputes: Paragraph 6 applies. Where paragraph 6 applies, the respective nominees of the parties are:
 - Employer's nominee: TBC.
 - Contractor's nominee: _____.Or such replacement as each party may notify to the other from time to time.

Article 7 - ARBITRATION

- Article 7 and Schedule 1 apply.

Clause 2.2 - COMMENCEMENT AND COMPLETION

- Date for Commencement of the Works: 06/03/2017.
- Date for Completion: 19/05/2017.

Clause 2.8 - LIQUIDATED DAMAGES

- At the rate of £150 per calendar week or pro-rata thereto.

Clause 2.10 - RECTIFICATION PERIOD

- Period: 12 months from the date of practical completion.

Clause 4.3 - PERCENTAGE OF THE TOTAL VALUE OF THE WORK ETC.

- Percentage: 95 per cent.

Clause 4.4 - PERCENTAGE OF THE TOTAL AMOUNT TO BE PAID TO THE CONTRACTOR

- Percentage: 97½ per cent.

Clause 4.8.1 - SUPPLY OF DOCUMENTATION FOR COMPUTATION OF AMOUNT TO BE FINALLY CERTIFIED

- Period: Three months from the date of practical completion.

Clause 4.11 and Schedule 2 - CONTRIBUTION, LEVY AND TAX CHANGES

- Clause 4.11 and Schedule 2 will be deleted.

Clause 5.3.2 - CONTRACTOR'S INSURANCE - INJURY TO PERSONS OR PROPERTY

- Insurance cover (for any one occurrence or series of occurrences arising out of one event): Not less than £5,000,000.

Clauses 5.4A, 5.4B and 5.4C - INSURANCE OF THE WORKS ETC - ALTERNATIVE PROVISIONS

- Clause do not applies.

Clauses 5.4A.1 and 5.4B.1.2 - PERCENTAGE TO COVER PROFESSIONAL FEES

- Addition: 15 per cent.

Clause 7.2 - ADJUDICATION

- The Adjudicator is: RICS.
- Nominating body: Royal Institution of Chartered Surveyors.

Schedule 1 paragraph 2.1 - ARBITRATION

- Appointor of Arbitrator (and of any replacement): President or a Vice president of the: The Royal Institution of Chartered Surveyors.

THE CONDITIONS

SECTION 1: DEFINITIONS AND INTERPRETATION

SECTION 2: CARRYING OUT THE WORKS

SECTION 3: CONTROL OF THE WORKS

SECTION 4: PAYMENT

SECTION 5: INJURY, DAMAGE AND INSURANCE

SECTION 6: TERMINATION

SECTION 7: SETTLEMENT OF DISPUTES

EXECUTION

- The Contract: Will be executed as a deed.

A30 TENDERING/ SUBLETTING/ SUPPLY

MAIN CONTRACT TENDERING

110 SCOPE

- General: These conditions are supplementary to those stated in the Invitation to Tender and on the form of tender.

160 EXCLUSIONS

- Inability to tender: Immediately inform if any parts of the work as defined in the tender documents cannot be tendered.
- Relevant parts of the work: Define those parts, stating reasons for the inability to tender.

170 ACCEPTANCE OF TENDER

- Acceptance: No guarantee is offered that any tender will be recommended for acceptance or be accepted, or that reasons for non acceptance will be given.
- Costs: No liability is accepted for any cost incurred in the preparation of any tender.

190 PERIOD OF VALIDITY

- Period: After submission or lodgement, keep tender open for consideration (unless previously withdrawn) for not less than 1 month.
- Date for possession/ commencement: See section A20.

PRICING/ SUBMISSION OF DOCUMENTS

210 PRELIMINARIES IN THE SPECIFICATION

- The Preliminaries/ General conditions sections (A10-A56 inclusive) must not be relied on as complying with SMM7/ NRM2.

250 PRICED DOCUMENTS

- Alterations: Do not alter or qualify the priced documents without written consent. Tenders containing unauthorised alterations or qualifications may be rejected.
- Measurements: Where not stated, ascertain from the drawings.
- Deemed included: Costs relating to items, which are not priced, will be deemed to have been included elsewhere in the tender.
- Submit: With tender.

310 TENDER

- General: Tenders must include for all work shown or described in the tender documents as a whole or clearly apparent as being necessary for the complete and proper execution of the Works.

510 ALTERNATIVE METHOD TENDERS

- General: In addition to and at the same time as tendering for the Works as defined in the tender documents, alternative methods of construction/ installation may be submitted for consideration. Alternatives, which would involve significant changes to other work, may not be considered.
- Alternative tenders: Such alternatives will be deemed to be alternative tenders and each must include a complete and precise statement of the effects on cost and programme.
- Safety method statement: Carry out a health and safety risk assessment for each alternative and where appropriate provide a safety method statement suitable for incorporation in the Health and Safety Plan.
- Full technical data: Submit for each alternative together with details of any consequential amendments to the design and/ or construction of other parts of the Works.
- Submit: With tender.

530 SUBSTITUTE PRODUCTS

- Details: If products of different manufacture to those specified are proposed, submit details with the tender giving reasons for each proposed substitution. Substitutions, which have not been notified at tender stage, may not be considered.
- Compliance: Substitutions accepted will be subject to the verification requirements of clause A31/200.

550 HEALTH AND SAFETY INFORMATION

- Content: Describe the organisation and resources to safeguard the health and safety of operatives, including those of subcontractors, and of any person whom the Works may affect.
- Include:
 - A copy of the contractor's health and safety policy document, including risk assessment procedures.
 - Accident and sickness records for the past five years.
 - Records of previous Health and Safety Executive enforcement action.
 - Records of training and training policy.
 - The number and type of staff responsible for health and safety on this project with details of their qualifications and duties.
- Submit: Within one week of request.

570 OUTLINE CONSTRUCTION PHASE HEALTH AND SAFETY PLAN

- Content: Submit the following information within one week of request:
 - Method statements on how risks from hazards identified in the pre-construction information and other hazards identified by the contractor will be addressed.
 - Details of the management structure and responsibilities.
 - Arrangements for issuing health and safety directions.
 - Procedures for informing other contractors and employees of health and safety hazards.
 - Selection procedures for ensuring competency of other contractors, the self-employed and designers.
 - Procedures for communications between the project team, other contractors and site operatives.
 - Arrangements for cooperation and coordination between contractors.
 - Procedures for carrying out risk assessment and for managing and controlling the risk.
 - Emergency procedures including those for fire prevention and escape.
 - Arrangements for ensuring that all accidents, illness and dangerous occurrences are recorded.
 - Arrangements for welfare facilities.
 - Procedures for ensuring that all persons on site have received relevant health and safety information and training.
 - Arrangements for consulting with and taking the views of people on site.
 - Arrangements for preparing site rules and drawing them to the attention of those affected and ensuring their compliance.
 - Monitoring procedures to ensure compliance with site rules, selection and management procedures, health and safety standards and statutory requirements.
 - Review procedures to obtain feedback.

SUBLETTING/ SUPPLY

A31 PROVISION, CONTENT AND USE OF DOCUMENTS

DEFINITIONS AND INTERPRETATIONS

110 DEFINITIONS

- Meaning: Terms, derived terms and synonyms used in the preliminaries/ general conditions and specification are as stated therein or in the appropriate British Standard or British Standard glossary.

120 COMMUNICATION

- Definition: Includes advise, inform, submit, give notice, instruct, agree, confirm, seek or obtain information, consent or instructions, or make arrangements.
- Format: In writing to the person named in clause A10/140 unless specified otherwise.
- Response: Do not proceed until response has been received.

130 PRODUCTS

- Definition: Materials, both manufactured and naturally occurring, and goods, including components, equipment and accessories, intended for the permanent incorporation in the Works.
- Includes: Goods, plant, materials, site materials and things for incorporation into the Works.

135 SITE EQUIPMENT

- Definition: All appliances or things of whatsoever nature required in or about the construction for completion of the Works but not materials or other things intended to form or forming part of the Permanent Works.
- Includes: Construction appliances, vehicles, consumables, tools, temporary works, scaffolding, cabins and other site facilities.

140 DRAWINGS

- Definitions: To BSRIA BG 6 A design framework for building services. Design activities and drawing definitions.
- CAD data: In accordance with BS 1192.

145 CONTRACTOR'S CHOICE

- Meaning: Selection delegated to the Contractor, but liability to remain with the specifier.

155 SUBMIT PROPOSALS

- Meaning: Submit information in response to specified requirements.

160 TERMS USED IN SPECIFICATION

- Remove: Disconnect, dismantle as necessary and take out the designated products or work and associated accessories, fixings, supports, linings and bedding materials. Dispose of unwanted materials. Excludes taking out and disposing of associated pipework, wiring, ductwork or other services.
- Fix: Receive, unload, handle, store, protect, place and fasten in position and disposal of waste and surplus packaging including all labour, materials and site equipment for that purpose.
- Supply and fix: As above, but including supply of products to be fixed. All products to be supplied and fixed unless stated otherwise.
- Keep for reuse: Do not damage designated products or work. Clean off bedding and jointing materials. Stack neatly, adequately protect and store until required by the Employer/ Purchaser or for use in the Works as instructed.
- Make good: Execute local remedial work to designated work. Make secure, sound and neat. Excludes redecoration and/ or replacement.
- Replace: Supply and fix new products matching those removed. Execute work to match original new state of that removed.
- Repair: Execute remedial work to designated products. Make secure, sound and neat. Excludes redecoration and/ or replacement.
- Refix: Fix removed products.
- Ease: Adjust moving parts of designated products or work to achieve free movement and good fit in open and closed positions.
- Match existing: Provide products and work of the same appearance and features as the original, excluding ageing and weathering. Make joints between existing and new work as inconspicuous as possible.
- System: Equipment, accessories, controls, supports and ancillary items, including installation, necessary for that section of the work to function.

170 MANUFACTURER AND PRODUCT REFERENCE

- Definition: When used in this combination:
 - Manufacturer: The firm under whose name the particular product is marketed.
 - Product reference: The proprietary brand name and/ or reference by which the particular product is identified.
- Currency: References are to the particular product as specified in the manufacturer's technical literature current on the date of the invitation to tender.

200 SUBSTITUTION OF PRODUCTS

- Products: If an alternative product to that specified is proposed, obtain approval before ordering the product.
- Reasons: Submit reasons for the proposed substitution.
- Documentation: Submit relevant information, including:
 - manufacturer and product reference;
 - cost;
 - availability;
 - relevant standards;
 - performance;
 - function;
 - compatibility of accessories;
 - proposed revisions to drawings and specification;
 - compatibility with adjacent work;
 - appearance;
 - copy of warranty/ guarantee.
- Alterations to adjacent work: If needed, advise scope, nature and cost.
- Manufacturers' guarantees: If substitution is accepted, submit before ordering products.

210 CROSS REFERENCES

- Accuracy: Check remainder of the annotation or item description against the terminology used in the section or clause referred to.
- Related terminology: Where a numerical cross-reference is not given the relevant sections and clauses of the specification will apply.
- Relevant clauses: Clauses in the referred to specification section dealing with general matters, ancillary products and execution also apply.
- Discrepancy or ambiguity: Before proceeding, obtain clarification or instructions.

220 REFERENCED DOCUMENTS

- Conflicts: Specification prevails over referenced documents.

230 EQUIVALENT PRODUCTS

- Inadvertent omission: Wherever products are specified by proprietary name the phrase 'or equivalent' is to be deemed included.

240 SUBSTITUTION OF STANDARDS

- Specification to British Standard or European Standard: Substitution may be proposed complying with a grade or category within a national standard of another Member State of the European Community or an international standard recognised in the UK.
- Before ordering: Submit notification of all such substitutions.
- Documentary evidence: Submit for verification when requested as detailed in clause A31/200. Any submitted foreign language documents must be accompanied by certified translations into English.

250 CURRENCY OF DOCUMENTS

- Currency: References to published documents are to the editions, including amendments and revisions, current on the date of the Invitation to Tender.

260 SIZES

- General dimensions: Products are specified by their co-ordinating sizes.
- Timber: Cross section dimensions shown on drawings are:
 - Target sizes as defined in BS EN 336 for structural softwood and hardwood sections.
 - Finished sizes for non-structural softwood or hardwood sawn and further processed sections.

DOCUMENTS PROVIDED ON BEHALF OF THE EMPLOYER

- 410 ADDITIONAL COPIES OF DRAWINGS/ DOCUMENTS
- Additional copies: Issued free of charge.
- 440 DIMENSIONS
- Scaled dimensions: Do not rely on.
- 450 MEASURED QUANTITIES
- Ordering products and constructing the Works: The accuracy and sufficiency of the measured quantities is not guaranteed.
 - Precedence: The specification and drawings shall override the measured quantities.
- 460 THE SPECIFICATION
- Coordination: All sections must be read in conjunction with Main Contract Preliminaries/ General conditions.

DOCUMENTS PROVIDED BY CONTRACTOR/ SUBCONTRACTORS/ SUPPLIERS

- 630 TECHNICAL LITERATURE
- Information: Keep on site for reference by all supervisory personnel:
 - Manufacturers' current literature relating to all products to be used in the Works.
 - Relevant British, EN or ISO Standards.
- 640 MAINTENANCE INSTRUCTIONS AND GUARANTEES
- Components and equipment: Obtain or retain copies, register with manufacturer and hand over on or before completion of the Works.
 - Information location: In Building Manual.
 - Emergency call out services: Provide telephone numbers for use after completion. Extent of cover: twenty four hours seven days a week.

A32 MANAGEMENT OF THE WORKS

GENERALLY

- 110 SUPERVISION
- General: Accept responsibility for coordination, supervision and administration of the Works, including subcontracts.
 - Coordination: Arrange and monitor a programme with each subcontractor, supplier, local authority and statutory undertaker, and obtain and supply information as necessary for coordination of the work.
- 120 INSURANCE
- Documentary evidence: Before starting work on site submit details, and/ or policies and receipts for the insurances required by the Conditions of Contract.
- 130 INSURANCE CLAIMS
- Notice: If any event occurs which may give rise to any claim or proceeding in respect of loss or damage to the Works or injury or damage to persons or property arising out of the Works, immediately give notice to the Employer, the person named in clause A10/140 and the Insurers.
 - Failure to notify: Indemnify the Employer against any loss, which may be caused by failure to give such notice.

140 CLIMATIC CONDITIONS

- Information: Record accurately and retain:
 - Daily maximum and minimum air temperatures (including overnight).
 - Delays due to adverse weather, including description of the weather, types of work affected and number of hours lost.

150 OWNERSHIP

- Alteration/ clearance work: Materials arising become the property of the Contractor except where otherwise stated. Remove from site as work proceeds.

PROGRAMME/ PROGRESS

210 PROGRAMME

- Master programme: Immediately when requested and before starting work on site submit in an approved form a master programme for the Works, which must include details of:
 - Planning and mobilisation by the Contractor
 - Subcontractor's work.
 - Running in, adjustment, commissioning and testing of all engineering services and installations.
 - Work resulting from instructions issued in regard to the expenditure of provisional sums.
 - Work by others concurrent with the Contract.
- Submit one copy.

245 START OF WORK ON SITE

- Notice: Before the proposed date for start of work on site give minimum notice of one week.

260 SITE MEETINGS

- General: Site meetings will be held to review progress and other matters arising from administration of the Contract.
- Frequency: Every two weeks.
- Location: On Site.
- Accommodation: Ensure availability at the time of such meetings.
- Attendees: Attend meetings and inform subcontractors and suppliers when their presence is required.
- Chairperson (who will also take and distribute minutes): Contract Administrator.

290 NOTICE OF COMPLETION

- Requirement: Give notice of the anticipated dates of completion of the whole or parts of the Works.
- Associated works: Ensure necessary access, services and facilities are complete.
- Period of notice (minimum): Two weeks.

310 EXTENSIONS OF TIME

- Notice: When a notice of the cause of any delay or likely delay in the progress of the works is given under the contract, written notice must also be given of all other causes which apply concurrently.
- Details: As soon as possible submit:
 - Relevant particulars of the expected effects, if appropriate, related to the concurrent causes.
 - An estimate of the extent, if any, of the expected delay in the completion of the Works beyond the date for completion.
 - All other relevant information required.

CONTROL OF COST

- 420 REMOVAL/ REPLACEMENT OF EXISTING WORK
- Extent and location: Agree before commencement.
 - Execution: Carry out in ways that minimize the extent of work.
- 430 PROPOSED INSTRUCTIONS
- Estimates: If a proposed instruction requests an estimate of cost, submit without delay and in any case within seven days.
- 440 MEASUREMENT
- Covered work: Give notice before covering work required to be measured.
- 470 PRODUCTS NOT INCORPORATED INTO THE WORKS
- Ownership: At the time of each valuation, supply details of those products not incorporated into the Works which are subject to any reservation of title inconsistent with passing of property as required by the Conditions of Contract, together with their respective values.
 - Evidence: When requested, provide evidence of freedom of reservation of title.

A33 QUALITY STANDARDS/ CONTROL

STANDARDS OF PRODUCTS AND EXECUTIONS

- 110 INCOMPLETE DOCUMENTATION
- General: Where and to the extent that products or work are not fully documented, they are to be:
 - Of a kind and standard appropriate to the nature and character of that part of the Works where they will be used.
 - Suitable for the purposes stated or reasonably to be inferred from the project documents.
 - Contract documents: Omissions or errors in description and/ or quantity shall not vitiate the Contract nor release the Contractor from any obligations or liabilities under the Contract.
- 120 WORKMANSHIP SKILLS
- Operatives: Appropriately skilled and experienced for the type and quality of work.
 - Registration: With Construction Skills Certification Scheme.
 - Evidence: Operatives must produce evidence of skills/ qualifications when requested.
- 130 QUALITY OF PRODUCTS
- Generally: New. (Proposals for recycled products may be considered).
 - Supply of each product: From the same source or manufacturer.
 - Whole quantity of each product required to complete the Works: Consistent kind, size, quality and overall appearance.
 - Tolerances: Where critical, measure a sufficient quantity to determine compliance.
 - Deterioration: Prevent. Order in suitable quantities to a programme and use in appropriate sequence.

135 QUALITY OF EXECUTION

- Generally: Fix, apply, install or lay products securely, accurately, plumb, neatly and in alignment.
- Colour batching: Do not use different colour batches where they can be seen together.
- Dimensions: Check on-site dimensions.
- Finished work: Without defects, e.g. not damaged, disfigured, dirty, faulty, or out of tolerance.
- Location and fixing of products: Adjust joints open to view so they are even and regular.

140 COMPLIANCE

- Compliance with proprietary specifications: Retain on site evidence that the proprietary product specified has been supplied.
- Compliance with performance specifications: Submit evidence of compliance, including test reports indicating:
 - Properties tested.
 - Pass/ fail criteria.
 - Test methods and procedures.
 - Test results.
 - Identity of testing agency.
 - Test dates and times.
 - Identities of witnesses.
 - Analysis of results.

150 INSPECTIONS

- Products and executions: Inspection or any other action must not be taken as approval unless confirmed in writing referring to:
 - Date of inspection.
 - Part of the work inspected.
 - Respects or characteristics which are approved.
 - Extent and purpose of the approval.
 - Any associated conditions.

160 RELATED WORK

- Details: Provide all trades with necessary details of related types of work. Before starting each new type or section of work ensure previous related work is:
 - Appropriately complete.
 - In accordance with the project documents.
 - To a suitable standard.
 - In a suitable condition to receive the new work.
- Preparatory work: Ensure all necessary preparatory work has been carried out.

170 MANUFACTURER'S RECOMMENDATIONS/ INSTRUCTIONS

- General: Comply with manufacturer's printed recommendations and instructions current on the date of the Invitation to tender.
- Changes to recommendations or instructions: Submit details.
- Ancillary products and accessories: Use those supplied or recommended by main product manufacturer.
- Agrément certified products: Comply with limitations, recommendations and requirements of relevant valid certificates.

180 WATER FOR THE WORKS

- Mains supply: Clean and uncontaminated.
- Other: Do not use until:
 - Evidence of suitability is provided.
 - Tested to BS EN 1008 if instructed.

SAMPLES/ APPROVALS

210 SAMPLES

- Products or executions: Comply with all other specification requirements and in respect of the stated or implied characteristics either:
 - To an express approval.
 - To match a sample expressly approved as a standard for the purpose.

220 APPROVAL OF PRODUCTS

- Submissions, samples, inspections and tests: Undertake or arrange to suit the Works programme.
- Approval: Relates to a sample of the product and not to the product as used in the Works. Do not confirm orders or use the product until approval of the sample has been obtained.
- Complying sample: Retain in good, clean condition on site. Remove when no longer required.

230 APPROVAL OF EXECUTION

- Submissions, samples, inspections and tests: Undertake or arrange to suit the Works programme.
- Approval: Relates to the stated characteristics of the sample. (If approval of the finished work as a whole is required this is specified separately). Do not conceal, or proceed with affected work until compliance with requirements is confirmed.
- Complying sample: Retain in good, clean condition on site. Remove when no longer required.

ACCURACY/ SETTING OUT GENERALLY

320 SETTING OUT

- General: Submit details of methods and equipment to be used in setting out the Works.
- Levels and dimensions: Check and record the results on a copy of drawings. Notify discrepancies and obtain instructions before proceeding.
- Inform: When complete and before commencing construction.

330 APPEARANCE AND FIT

- Tolerances and dimensions: If likely to be critical to execution or difficult to achieve, as early as possible either:
 - Submit proposals; or
 - Arrange for inspection of appearance of relevant aspects of partially finished work.
- General tolerances (maximum): To BS 5606, tables 1 and 2.

540 DEFECTS IN EXISTING WORK

- Undocumented defects: When discovered, immediately give notice. Do not proceed with affected related work until response has been received.
- Documented remedial work: Do not execute work which may:
 - Hinder access to defective products or work; or
 - Be rendered abortive by remedial work.

610 DEFECTIVE PRODUCTS/ EXECUTIONS

- Proposals: Immediately any work or product is known, or appears, to be not in accordance with the Contract, submit proposals for opening up, inspection, testing, making good, adjustment of the Contract Sum, or removal and re-execution.
- Acceptability: Such proposals may be unacceptable and contrary instructions may be issued.

WORK AT OR AFTER COMPLETION

710 WORK BEFORE COMPLETION

- General: Make good all damage consequent upon the Works.
Temporary markings, coverings and protective wrappings: Remove unless otherwise instructed.
- Cleaning: Clean the Works thoroughly inside and out, including all accessible ducts and voids. Remove all splashes, deposits, efflorescence, rubbish and surplus materials.
- Cleaning materials and methods: As recommended by manufacturers of products being cleaned, and must not damage or disfigure other materials or construction.
- COSHH dated data sheets: Obtain for all materials used for cleaning and ensure they are used only as recommended by their manufacturers.
- Minor faults: Touch up in newly painted work, carefully matching colour and brushing out edges. Repaint badly marked areas back to suitable breaks or junctions.
- Moving parts of new work: Adjust, ease and lubricate as necessary to ensure easy and efficient operation, including doors, windows, drawers, ironmongery, appliances, valves and controls.

730 MAKING GOOD DEFECTS

- Remedial work: Arrange access with Contract Administrator.
- Rectification: Give reasonable notice for access to the various parts of the Works.
- Completion: Notify when remedial works have been completed.

A34 SECURITY/ SAFETY/ PROTECTION

SECURITY, HEALTH AND SAFETY

140 CONSTRUCTION PHASE HEALTH AND SAFETY PLAN

- Submission: Present to the Employer/ Client no later than one week before commencement.
- Confirmation: Do not start construction work until the Employer has confirmed in writing that the Construction Phase Health and Safety Plan includes the procedures and arrangements required by the CDM Regulations.
- Content: Develop the plan from and draw on the Outline Construction Phase Health and Safety Plan, clause A30/570, and the Pre-tender Health and Safety Plan/ Preconstruction information.

150 SECURITY

- Protection: Safeguard the site, the Works, products, materials, and any existing buildings affected by the Works from damage and theft.
- Access: Take all reasonable precautions to prevent unauthorized access to the site, the Works and adjoining property.
- Special requirements: Prevent general public gaining access the areas of work..

160 STABILITY

- Responsibility: Maintain the stability and structural integrity of the Works and adjacent structures during the Contract.
- Design loads: Obtain details, support as necessary and prevent overloading.

170 OCCUPIED PREMISES

- Extent: Existing buildings will be occupied and/ or used during the Contract as follows: County Sessions House and Walker Art Gallery.
- Works: Carry out without undue inconvenience and nuisance and without danger to occupants and users.
- Overtime: If compliance with this clause requires certain operations to be carried out during overtime, and such overtime is not required for any other reason, the extra cost will be allowed, provided that such overtime is authorized in advance.

180 ACCESS CONTROL

- Controlled areas: Welfare facilities and booking in point.
- Control type: Access card with reader.
- Authorised persons: Submit a list of the names of all persons requiring access together with any other related information reasonably required.
- Return of credentials: When requested or on completion of the work to which the controlled area relates.

190 OCCUPIER'S RULES AND REGULATIONS

- Compliance: Conform to the occupier's rules and regulations affecting the site.
- Copies:
 - Location: on site.
 - Arrangements for inspection: CA.

210 EMPLOYER'S REPRESENTATIVES SITE VISITS

- Safety: Submit details in advance, to the Employer or the person identified in clause A10/140, of safety provisions and procedures (including those relating to materials, which may be deleterious), which will require their compliance when visiting the site.
- Protective clothing and/ or equipment: Provide and maintain on site for the Employer and the person stated in clause A10/140 and other visitors to the site.

220 WORKING PRECAUTIONS/ RESTRICTIONS

- Hazardous areas: Operatives must take precautions as follows:
 - Work area: public highway.
 - Precautions: exclude general public.
- Permit to work: Operatives must comply with procedures in the following areas:
 - Work area: NA.
 - Procedures: NA.

PROTECT AGAINST THE FOLLOWING

340 POLLUTION

- Prevention: Protect the site, the Works and the general environment including the atmosphere, land, streams and waterways against pollution.
- Contamination: If pollution occurs inform immediately, including to the appropriate Authorities and provide relevant information.

360 NUISANCE

- Duty: Prevent nuisance from smoke, dust, rubbish, vermin and other causes.
- Surface water: Prevent hazardous build-up on site, in excavations and to surrounding areas and roads.

- 370 ASBESTOS CONTAINING MATERIALS
- Duty: Report immediately any suspected materials discovered during execution of the Works.
 - Do not disturb.
 - Agree methods for safe removal or encapsulation.
- 371 DANGEROUS OR HAZARDOUS SUBSTANCES
- Duty: Report immediately suspected materials discovered during execution of the Works.
 - Do not disturb.
 - Agree methods for safe removal or remediation.
- 380 FIRE PREVENTION
- Duty: Prevent personal injury or death, and damage to the Works or other property from fire.
 - Standard: Comply with Joint Code of Practice 'Fire Prevention on Construction Sites', published by Construction Industry Publications and The Fire Protection Association (The 'Joint Fire Code').
- 390 SMOKING ON SITE
- Smoking on site: Not permitted.
- 400 BURNING ON SITE
- Burning on site: Not permitted.
- 410 MOISTURE
- Wetness or dampness: Prevent, where this may cause damage to the Works.
 - Drying out: Control humidity and the application of heat to prevent:
 - Blistering and failure of adhesion.
 - Damage due to trapped moisture.
 - Excessive movement.
- 430 WASTE
- Includes: Rubbish, debris, spoil, surplus material, containers and packaging.
 - General: Minimize production. Prevent accumulations. Keep the site and Works clean and tidy.
 - Handling: Collect and store in suitable containers. Remove frequently and dispose off site in a safe and competent manner:
 - Non-hazardous material: In a manner approved by the Waste Regulation Authority.
 - Hazardous material: As directed by the Waste Regulation Authority and in accordance with relevant regulations.
 - Recyclable material: Sort and dispose at a Materials Recycling Facility approved by the Waste Regulation Authority.
 - Voids and cavities in the construction: Remove rubbish, dirt and residues before closing in.
 - Waste transfer documentation: Retain on site.
- 440 ELECTROMAGNETIC INTERFERENCE
- Duty: Prevent excessive electromagnetic disturbance to apparatus outside the site.
- 460 POWER ACTUATED FIXING SYSTEMS
- Use: Not permitted.

PROTECT THE FOLLOWING

510 EXISTING SERVICES

- Confirmation: Notify all service authorities, statutory undertakers and/ or adjacent owners of proposed works not less than one week before commencing site operations.
- Identification: Before starting work, check and mark positions of utilities/ services. Where positions are not shown on drawings obtain relevant details from service authorities, statutory undertakers or other owners.
- Work adjacent to services:
 - Comply with service authority's/ statutory undertaker's recommendations.
 - Adequately protect, and prevent damage to services: Do not interfere with their operation without consent of service authorities/ statutory undertakers or other owners.
- Identifying services:
 - Below ground: Use signboards, giving type and depth;
 - Overhead: Use headroom markers.
- Damage to services: If any results from execution of the Works:
 - Immediately give notice and notify appropriate service authority/ statutory undertaker.
 - Make arrangements for the work to be made good without delay to the satisfaction of service authority/ statutory undertaker or other owner as appropriate.
 - Any measures taken to deal with an emergency will not affect the extent of the Contractor's liability.
- Marker tapes or protective covers: Replace, if disturbed during site operations, to service authority's/ statutory undertakers recommendations.

520 ROADS AND FOOTPATHS

- Duty: Maintain roads and footpaths within and adjacent to the site and keep clear of mud and debris.
- Damage caused by site traffic or otherwise consequent upon the Works: Make good to the satisfaction of the Employer, Local Authority or other owner.

540 RETAINED TREES/ SHRUBS/ GRASSED AREAS

- Protection: Preserve and prevent damage, except those not required.
- Replacement: Mature trees and shrubs if uprooted, destroyed, or damaged beyond reasonable chance of survival in their original shape, as a consequence of the Contractor's negligence, must be replaced with those of a similar type and age at the Contractor's expense.

550 RETAINED TREES

- Protected area: Unless agreed otherwise do not:
 - Dump spoil or rubbish, excavate or disturb topsoil, park vehicles or plant, store materials or place temporary accommodation within an area which is the larger of the branch spread of the tree or an area with a radius of half the tree's height, measured from the trunk.
 - Sever roots exceeding 25 mm in diameter. If unintentionally severed give notice and seek advice.
 - Change level of ground within an area 3 m beyond branch spread.

560 EXISTING FEATURES

- Protection: Prevent damage to existing buildings, fences, gates, walls, roads, paved areas and other site features, which are to remain in position during execution of the Works.
- Special requirements: Landscaped areas.

- 570 EXISTING WORK
- Protection: Prevent damage to existing work, structures or other property during the course of the work.
 - Removal: Minimum amount necessary.
 - Replacement work: To match existing.
- 610 ESPECIALLY VALUABLE/ VULNERABLE ITEMS
- Protection: Ensure provision and maintenance of special protective measures to prevent damage to the following:
 - Stonework generally.
 - Method statement: Submit within one week of request describing special protection to be provided.
- 620 ADJOINING PROPERTY
- Permission: Obtain as necessary from owners if requiring to erect scaffolding on or otherwise use adjoining property.
- 625 ADJOINING PROPERTY RESTRICTIONS
- Precautions:
 - Prevent trespass of workpeople and take precautions to prevent damage to adjoining property.
 - Pay all charges.
 - Remove and make good on completion or when directed.
 - Damage: Bear cost of repairing damage arising from execution of the Works.
- 630 EXISTING STRUCTURES
- Duty: Check proposed methods of work for effects on adjacent structures inside and outside the site boundary.
 - Supports: During execution of the Works:
 - Provide and maintain all incidental shoring, strutting, needling and other supports as may be necessary to preserve stability of existing structures on the site or adjoining, that may be endangered or affected by the Works.
 - Do not remove until new work is strong enough to support existing structure.
 - Prevent overstressing of completed work when removing supports.
 - Adjacent structures: Monitor and immediately report excessive movement.
 - Standard: Comply with BS 5975 and BS EN 12812.
- 640 MATERIALS FOR RECYCLING/ REUSE
- Duty: Sort and prevent damage to stated products or materials, clean off bedding and jointing materials and other contaminants.
 - Storage: Stack neatly and protect until required by the Employer or for use in the Works as instructed.

A35 SPECIFIC LIMITATIONS ON METHOD/ SEQUENCE/ TIMING

- 130 METHOD/ SEQUENCE OF WORK
- Specific Limitations: Include the following in the programme:
 - Only dismantle balustrade once new components have been manufactured..
- 160 USE OR DISPOSAL OF MATERIALS
- Specific limitations: Materials for disposal should be removed by the end of each working day..

- 170 WORKING HOURS
- Specific limitations: 8.00 - 17.00.

A36 FACILITIES/ TEMPORARY WORK/ SERVICES

GENERALLY

- 110 SPOIL HEAPS, TEMPORARY WORKS AND SERVICES
- Location: Give notice and details of intended siting.
 - Maintenance: Alter, adapt and move as necessary. Remove when no longer required and make good.

ACCOMMODATION

- 230 TEMPORARY ACCOMMODATION
- Accommodation made available by the Employer: The following may be used for the duration of the Contract without charge provided that:
 - It is used solely for the purposes of carrying out the Works.
 - The use to which it is put does not involve undue risk of damage.
 - Any temporary adaptations are approved by or on behalf of the Employer before being carried out.
 - It is vacated on completion of the Works or determination of the Contract.
 - When vacated, its condition is at least equivalent to its condition at the start of the Contract.
 - Description: Welfare facilities at Walker Art Gallery.
 - Available services and facilities: Toilet, washing facilities..

TEMPORARY WORKS

- 340 NAME BOARDS/ ADVERTISEMENTS
- Name boards/ advertisements: Not permitted.

SERVICES AND FACILITIES

- 440 TELEPHONES
- Direct communication: As soon as practicable after the Date of Possession provide the Contractor's person in charge with a mobile telephone.

A37 OPERATION/ MAINTENANCE OF THE FINISHED WORKS

A40 CONTRACTOR'S GENERAL COST ITEMS: MANAGEMENT AND STAFF

A41 CONTRACTOR'S GENERAL COST ITEMS: SITE ACCOMMODATION

A50 WORK/ PRODUCTS BY/ ON BEHALF OF THE EMPLOYER

A53 WORK BY STATUTORY AUTHORITIES/ UNDERTAKERS

A54 PROVISIONAL WORK/ ITEMS

110 PROVISIONAL SUMS FOR DEFINED WORK

- Item: Stonework repairs.
- Description of work: Stoneworks repairs as directed on site.
- Provisional Sums: Include £2,000.
- Allow for general attendance.

590 CONTINGENCIES

- Provisional sum: Include: £2,000.

A55 DAYWORKS