

Price List

Name 601704 - A30 BD Monkton - Rawridge MP 239.5 - 247 FHS

Contractor

Guidance notes & preamble for the Contractor

The Contractor is paid in accordance with Clause 50 & 51. The rates and prices entered in the Price List shall be deemed to be the full inclusive value of the work covered by the items

You are required to submit a Rate or Price for each Item associated with the Providing the Works

Where an Item has specified Quantity, you should enter a value in the Rate column and the Price for each Item should be equal to the specified Quantity multiplied by your submitted Rate. Payment for these items will be made in accordance with the Contract i.e. total Quantity completed multiplied by the Rate.

For Items where the unit is specified as 'lump sum' you should submit a Price only.

All Rates and Prices must be quoted in pounds and whole new pence to two decimal places and exclude VAT. Any item priced as zero must be

You should ensure the total is correct before submission, if necessary, the Employer may contact a tenderer whose Offer has required an arithmetical adjustment.

Price List Part 2

Item No.	Item Description	Unit	Quantity	Rate	Price
1.01	Mobilisation and site set-up	No	1	£0.00	£0.00
1.02	Drainage Survey to be carried out to the existing drainage system within the scheme extents as shown on drawings HE601704-KIER-VDS-A30_MP239.5 - MP245.9-DR-CD-0500_01 to 06 and as specified in National Asset Delivery TST works information, Section 6 - Specification for the Works. The Drainage Survey is to include the following survey types; validation survey, priority asset survey, all assets condition and connectivity survey, pipework and chambers defect survey by CCTV.	m	14,100	£0.00	£0.00
1.03	Vegetation clearance to be carried out where required to facilitate drainage survey works. Indicative locations where Vegetation Clearance may be required are shown on drawings HE601704-KIER-HSC-A30_MP239.5 - MP245.9-DR-CD-0100_01 to 06. Price to include for requirement for Ecological Clerk of Works (ECOW).	m²	25,415	£0.00	£0.00

1.04	Vegetation clearance along line of existing ditch to be carried out where required to facilitate drainage survey works. Indicative locations where Vegetation Clearance may be required are shown on drawings HE601704-KIER-HSC-A30_MP239.5 - MP245.9-DR-CD-0100_01 to 06. Price to include for requirement for Ecological Clerk of Works (ECoW).	m ²	2,798	£0.00	£0.00
1.05	Drainage Survey Results (Drainage Survey summary report in PDF and digital data format, Drainage Survey drawings in DXF and PDF format, Drainage Survey data to be packaged with a propriety viewer (Wincan VX) in addition to the standard data)	No	1	£0.00	£0.00
1.06	Drainage Survey data to be provided in HADDMS shape file format to upload to the Highways England Drainage Data Management System (HADDMS).	No	1	£0.00	£0.00
total of the Prices					£0.00