

**National Asset Delivery
Technical Surveys and Testing**

Works Information for

**East Area 605746 - A47 EB WB A1122
Rbt - Norwich Rd Swaffham –
Coring/DCP Survey**

CONTENTS AMENDMENT SHEET

Amend. No.	Revision No.	Amendments	Initials	Date
0	0	Original version issued with tender	JKP	21/06/21

TABLE OF CONTENTS

1 Description of the works4

2 Existing InformationError! Bookmark not defined.

3 Constraints on how the Contractor Provides the Works6

4 Requirements for the programme8

5 Services and other things provided by the *Employer*9

6 Specification for the works10

LIST OF ANNEXES

Appendix 1 Supplementary Constraints

1 DESCRIPTION OF THE WORKS

1.1 Project objectives

1.1.1 The principle objective of this project is to undertake coring and DCP testing as stated in, RRP0926 A47 EB WB A1122Rbt-NorwichRd Swaffham Survey Schedule. Provide a subsequent report in accordance with the requirements detailed in the specification.

1.1.2 The specification that applies to the works is included in Section 6

1.2 Scope of works

1.2.1 The works to be provided under this contract are:

Carry out coring in lane 1 and 2 (up to 30 cores/DCP per night), as per locations shown on the investigations plans supplied by Highways England. Cores to be 150mm diameter to full depth of bound layer with site photos taken of the extracted core and core hole. Carry out DCP testing in core holes as indicated on the investigation plans supplied by Highways England, where safe to do so.

Deliverables

1.2.2 The Contractor is required to produce the following deliverables:

- (1) All reporting to be in accordance with the requirements set out in CS 229
- (2) Produce a core log for each core.
- (3) Produce a DCP plot and layer table for each DCP test.
- (4) Provide a brief report on the results, with interpretation.
- (5) All results to be supplied in electronic format and in accordance with CS 229 DMRB

2 EXISTING INFORMATION

2.1.1 Refer to the site information for details of existing site conditions including ground conditions, limitation on access, position of existing structures etc.

Drawing Number	Title	Revision / Date
	RRP0926 A47 EB WB A1122Rbt-Norwich Rd Swaffham – excel document	21/06/2021

For Information Only
Do not complete at this stage

3 CONSTRAINTS ON HOW THE CONTRACTOR PROVIDES THE WORKS

3.1 General

- 3.1.1 The *Contractor* Provides the Works in such manner as to minimise the risk of damage or disturbance to or destruction of third party property.
- 3.1.2 The *Contractor* complies with the constraints and meets with the requirements outlined in Appendix 1.
- 3.1.3 The *Contractor* submits information detailing how the *Contractor* will provide the Works to the *Employer* prior to the *works* commencing. This information will include any lifting plans, risk assessments, method statements, the *Contractor's* staff training information and any other relevant Health and Safety requirements.

3.2 Working hours & site-specific constraints

- 3.2.1 The *Contractor's* working hours for site works shall be 8pm to 6am Monday to Friday
- 3.2.2 All work is on the A47 eastbound and westbound between the A1122 roundabout and Norwich Road Swaffham
- 3.2.3 TM to be provided by CWF

3.3 Health, Safety and Environment & Risk Management

Health and Safety requirements

- 3.3.1 In Providing the Works the *Contractor* meets the requirements of Annex 2 of the supplementary constraints in relation to health and safety duties.
- 3.3.2 When implemented, the *Contractor* shall comply with the requirements of Highways England's safety passport scheme and ensure that all of his employees, and any of his subcontractor's, are registered in accordance with the implementation of the scheme.
- 3.3.3 For details of the CDM duty holders, refer to the pre-construction information which is attached, CPP & other PCI to be provided upon successful tender.
- 3.3.4 Before commencing the construction phase of the *works*, the *Contractor* confirms to the *Employer* that adequate welfare facilities are in place. Where the facilities detailed in section 5 are not deemed adequate, the *Contractor* provides all necessary facilities to Provide the Works and to comply with the minimum requirements set out in HSE guidance document L153.

Environmental requirements

- 3.3.5 In Providing the Works the *Contractor* meets the requirements of Annex 2 of the supplementary constraints in relation to environmental duties.

Risk Management

- 3.3.6 The *Contractor* identifies, manages and mitigates risks in accordance with the principles of ISO31000.
- 3.3.7 The *Contractor* submits a risk register, which captures all risks associated with the delivery of the *works* including those identified by the *Employer*, with his tender and maintains it for the contract period.

For Information Only
Do not complete at this stage

4 REQUIREMENTS FOR THE PROGRAMME

- 4.1.1 The *Contractor* submits programme to the *Employer* with his tender.
- 4.1.2 The *Contractor* Provides the Works considering the following programme constraints:
- (i) the *starting date* and *completion date* and any post site works, reporting and review period
 - (ii) The services and other things provided by *Employer* (see Section 5)
 - (iii) Results to be issued within 2 weeks of completing site work or as soon as reasonably practicable.
- 4.1.3 The programme should be in the form of an activity and time related bar chart, produced as a result of a critical path analysis.
- 4.1.4 The programme should preferably be provided in either a PDF or MS Excel format and cover the full contract period including post site activities. Activities should be clearly defined and named, and the programme should detail the following:
- (i) dates and times associated with the project, including the *starting date*, *completion date* & *Contractor's* planned completion, and any other dates or times that will specifically impact the delivery of the project
 - (ii) activities associated with delivering the project
- 4.1.5 The *Contractor* updates the programme every 2 weeks. The *Contractor* submits an updated programme to the *Employer* upon request.

5 SERVICES AND OTHER THINGS PROVIDED BY THE *EMPLOYER*

5.1.1 The following temporary traffic management will be provided by the *Employer* to allow the *Contractor* to Provide the Works:

1. CWF to provide TM

Location	No of Shifts (Total Closure)	Number of Cores	Number of DCP
A47 EB A1122 Rbt-Norwich Rd Swaffham rsf	2 Shifts	54	32
A47 WB A1122 Rbt-Norwich Rd Swaffham rsf	2 Shifts	56	39

5.1.2 The other things that will be provided by the *Employer* are as follows:

(1) Welfare facilities will be provided by the principle contractor.

6 SPECIFICATION FOR THE WORKS

6.1.1 The *Contractor* shall undertake the works in accordance with:

6.1.2 CS 229 DMRB

For Information Only
Do not complete at this stage