

SITE VISIT REPORT

E. Indicative costs:

Item	Description	Unit	Number	£/unit	Cost (£)
1	Transport and Preliminaries	Item	1	£1,000.00	£1,000.00
2	Excavation and jetting of collector and main drain	Item	1	£1,600.00	£1,600.00
3	Installation of new inspection chamber	Item	1	£550.00	£550.00
4	Installation of slit drains at 0.5 m spacing	m ²	6,000	£2.10	£12,600.00
5	Disposal of soil arisings	Item	1	£2,000.00	£2,000.00
6	First sand topdressing (1 x 8 mm depth)	t	80	£38.00	£3,040.00
7	Application of fertiliser	m ²	6,000	£0.05	£300.00
8	Overseeding	m ²	6,000	£0.20	£1,200.00
9	Second sand topdressing (1 x 8 mm depth)	t	80	£38.00	£3,040.00
10	Third sand topdressing (1 x 8 mm depth)	t	80	£38.00	£3,040.00
				TOTAL (excl. VAT)	£28,370.00

F. Indicative work programme:

With respect to timescales for completing the work, it is recommended that this is only completed under suitable ground and weather conditions to avoid any potential performance-related problems later on.

Operation	2021											
	J	F	M	A	M	J	J	A	S	O	N	D
Mobilisation of Contractor(s)												
Excavation and jetting of collector and main drain												
Installation of new inspection chamber												
Installation of sand slits												
First sand topdressing (1 x 8 mm depth)												
Application of fertiliser												
Overseeding												
Second sand topdressing (1 x 8 mm depth)												
Third sand topdressing (1 x 8 mm depth)												
Ground ready for play												

N.B. The precise date for the return to play is highly dependent on the weather conditions that prevail during the works.