



Wavin Stormwater Management



CONNECT TO BETTER

Wavin Stormwater Management

Project Details			
Project Name	Cheddar Pavilion	Produced By	Kelly Clark
Client Name	Cheddar Parish Council		
Site Address	Sharpham Road, BS27 3DR	Date	11/09/2019

Modular Units and Tank Details - extension roof

Unit configuration

The following information provides an approximate calculation and some assumptions. If more accurate information is required, please contact our technical team.

Length	5m	5 units
Width	4m	8 units
Depth	0.4m	1 units
Total Number of Units	40 units	

Recommended Unit

Wavin recommend using the following unit for your installation.

Calculations

Site Details

Area	380m ²	Traffic Loading (Soakaway size based on 1:30 year Storm)	Non-Trafficked
Soil Type	Sand		
Groundwater Present	No		

Area Sales Manager

If you would like to find out how to purchase AquaCell Units, please contact your Area Sales Manager

Name	John Nichols
Phone Number	07966 333689

Aquacell Disclaimer

- All information generated by this tool is supplied in good faith and without charge to enable reasonable assessment of the practical performance of Wavin products.
- Wavin offers a program of continuous improvement and reserves the right to modify the specification of products without notice.
- All information in this publication is believed to be correct at time of preparation. However, no responsibility can be accepted for any errors or omissions. Final determination of the suitability of information or material for the use contemplated and the manner of the use is the sole responsibility of the user
- Calculations are based upon relevant industry standards in accordance with the Wallingford Procedure, and should be verified by a qualified engineer.