# Ganton Close, Leeds

## Site Clearance

**Notes:**

**1) Figured dimensions to be taken. Do not scale dimensions. Contractors must verify all dimensions on site before preparing shop drawings or commencing any work.**

**2) Copyright ©. This drawing must not be reproduced without the permission of The Leeds Groundwork Trust**

**Planting Notes**

**Poisonous plants:** Please note that we have made every effort to avoid use of poisonous plant materials on the site; however, it should be noted that consumption of any ornamental plant may lead to adverse symptoms.

## Legend

- Excavate grass/soil in preparation for hardworks
- Excavate flags in preparation for hardworks
- Excavate stone setts in preparation for hardworks
- Excavate concrete block paving in preparation for hardworks
- Excavate bitmac surfacing in preparation for hardworks
- Remove 1m high timber fence/gate
- Remove 1.8m high timber fence
- Remove 1.8m high steel/palisade fence
- Remove 1m high steel fence

**GROUNDWORK**
Groundwork Landscape Architecture
Environment and Business Centre,
Marlpin-Rees Avenue,
Morley, Leeds, LS27 9SL
Telephone: 0113 238 0601
Fax: 0113 252 5057
Web: www.landscapearchitecture-groundwork@leeds.org.uk

Landscape Institute Membership

CHANGING PLACES CHANGING LIVES

| Project | Title | | |
|---|---|---|---|
| Ganton Close, Leeds | Site Clearance | | |
| Client | Drawing No. | Date | Rev |
| Leeds Federated Housing Associatlon | 03 | 09-03-17 | - |
| Site code | Drawn | Checked | Scale |
| LS6 2NF | MW | AM | 1:200 @ A1 |